

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| Monument (County) | Located In | Corner Code // |
|---------------------------------------|----------------|----------------|
| 1. Public Land Survey | T 9N R 7W | D12 |
| | T 9N R 7W | D13 |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S 3E T 9N R 7W | 12 |
| | S T R | |
| 3. Miscellaneous Property in Sec | S T R | |
| | S T R | |
| 4. Lot No. | Recorded Plat | |
| 5. Private Claims | | |

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Gary C. Bilow, in a field survey on D12 February 19, 1993, 19
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

D12: Not set in 1837 GLO survey by Noah Brookfield. County Surveyor Daoust set a stake and crockery at the intersection of the quarter
lines in 1906. Daoust witnessed the stake to a Pine stump 20. N69 1/4W, 19-1/2 and an Oak 6. S48-1/4W, 9.
D13: Post set by US Deputy Surveyor Noah Brookfield in 1837, accessories a Pine 30, N12W, 20 links and a W Ash 10, N46E, 41 links.
County Surveyor Daoust found the decayed remains of a stake bottom agreeing with the remains of the US BT Pine 30, N12W, 20 links in
1906. Daoust drove a pine root stake and set a large stone by the side, witnessing an Oak 8, S23-3/4W, 7 links and a Pine stump, N20E,
72 links.
12: Not set in 1837 GLO survey by Noah Brookfield. County Surveyor Daoust reports setting a stake for the corner in 1906, witnesses to
a Pine stump 30, notches on post, N24 1/2E, 19 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D12: Found rotted stake and crockery. Stake is 4.7 north and 1.9 feet east of intersection of quarter lines. I consider Daoust's
survey as an original survey following correct procedures and therefore accept his stake and crockery as marking the true corner
location.
D13: Daoust's stake, stone and NEIs were not located. Corner established using 1906 proportional distances and Daoust's angle at the
corner. Distances are 0.02 longer than 1906 measure.
12: Daoust's stake and BT not found. Established corner mid-way and on line between D12 and D13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

| | | |
|---|---|--|
| D12: Replaced stake and crockery with 1/2"x36" rebar encased in a 4" diameter concrete cylinder capped with a cast aluminum Michigan Department of Natural Resources tablet S62E, 6.49, spike & tag in 8" W Oak S9E, 18.16, spike & tag in 7" W Oak S61W, 28.17, spike & tag in 9" W Oak N63W, 11.25, spike & tag in 7" W Oak | D13: Set 1/2"x36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources tablet S59E, 27.76, spike & tag in 14" R Oak S10E, 10.92, spike & tag in 4" W Pine N75W, 7.06, spike & tag in twin 14" Oak N51E, 16.61, 1/2" capped rebar - N1/4 section 5 per Wickan | 12: Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources tablet N50E, 9.82, spike & tag in 11" Maple S50E, 20.84, spike & tag in 12" W Oak S78W, 12.97, spike & tag in 12" W Oak N46W, 32.36, spike & tag in 12" W Cherry |
|---|---|--|

Signed by *Gary C. Bilow*
Surveyor's Michigan License No. 26453

Date 5/14/93

