

**MONTCALM COUNTY REMONUMENTATION PROGRAM**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

DEC 19 2000


SECTION

For corners in  
Montcalm  
 (County)

Located In:  
 Eureka Township

Corner Code #

- |                                    |       |              |                         |
|------------------------------------|-------|--------------|-------------------------|
| 1. Public Land Survey              | Sec 6 | T 09 N R 08W | <u>A-03</u> SW Corner   |
|                                    |       | T 09 R 09    | <u>M-03</u> <u>KENT</u> |
|                                    |       | T R          |                         |
|                                    |       | T R          |                         |
| 2. Property Controlling in Section | S     | T R          |                         |
|                                    | S     | T R          |                         |
| 3. Miscellaneous Property in Sec.  | S     | T R          |                         |
|                                    | S     | T R          |                         |



Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on May 8, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- May 26, 1837, Noah Brookfield, Deputy Surveyor, GLO Notes  
 Set Post  
 Yellow Oak 10" S21°W 56 links (39.96 feet)  
 Yellow oak 18" N77°W 77 links (50.82 feet)
- R.D. McNutt's Index Cards, T09N-R08W (#32)  
 White oak 10" N70°E 20 links (13.20 feet)  
 Aspen 20" S23°E 65 links (42.90 feet)
- July 1980, R.J. Crater, #16924, Liber 528, Page 245, Recorded Survey  
 Iron Rod  
 Oak 14" S30°W 40.10 feet  
 Maple 6" S45°E 41.00 feet  
 Twin Oak 30" N85°W 24.60 feet  
 Cherry 10" West 48.00 feet
- July 1980, R.J. Crater #16924, Liber 1, Page 518, Recorded LCRC  
 Found Stone for corner, Set rod  
 Black Oak 14" S30°W 40.10 feet  
 Sugar Maple 6" S45°E 41.00 feet  
 Fence wire S/S Tw 30" Oak N 85°W 24.60 feet  
 10" Cherry, Due West 48.00 feet
- 1987, John Bueche, #13027, LCRC 4534, Kent County Records  
 Found Iron two feet West of Centerline of Gravel Road North-south and on tree row West  
 Found Iron East 33.00 feet  
 Found 14" Black Oak S30°W 40.10 feet  
 Found 10" Cherry West 48.00 feet  
 Replaced iron and stone with Standard Kent County Monument 6" below grade  
 Set Tag and Nail in Southside 18" Cherry N85°W 48.25 feet  
 Set Tag and Nail in Southside Twin 30" Oak N80°W 25.19 feet  
 Set Tag and Nail in Southeast Side 16" Oak S40°W 40.09 feet  
 1/2" x 18" Rerod S80°E 33.16 feet  
 Set Tag and Nail in Northeast side 30" Maple S35°E 42.30 feet  
 Set Tag and Nail in Northeast side 6" Maple N65°E 49.75 feet



ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/11/00.


William Tingley  
 William Tingley, PS, Chairman

Continued on back

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 Searched the apparent location of the corner. Found Kent County Harrison monument.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 Kent Co. mon.  
 Fnd N/T S/S 18" Cherry N85°W 48.25 feet  
 Fnd N/T S/S 32" Twin Oak N80°W 25.19 feet  
 Fnd N/T SE/S 26" Oak S40°W 40.09 feet  
 Fnd 1/2" x 18" rerod S80°E 33.16 feet  
 Fnd N/T NE/S 30" Maple S35°E 42.30 feet

Bearings given are magnetic. This corner is accepted as the best available evidence of the position of the original corner

Signed by William Tingley Date 10/11/00  
 Surveyor's Michigan License No. 30104



Continued from front

6. 1990, R. Unema, #33987, Survey L231, Page 49 and L231, Page 48  
Same as LCRC 4534 except does not show Maples Southwest and Northeast

REPRODUCED FROM ORIGINAL

DEC 19 2000

SECTION

7. October 10, 1994, James C. Glaza # 40166, LCRC #7256  
Found Kent County monument.

- K.C. remon tag/nail S/S cherry 18" N85°W 48.04 feet
- K.C. remon tag/nail S/S tw oak 30" N80°W 25.21 feet
- K.C. remon tag/nail SE/S oak 18" S40°W 40.09 feet
- 1/2" x 18" rerod S80°E 33.12 feet
- K.C. remon tag/nail NE/S oak 27" S35°E 42.25 feet
- In centerline of gravel road
- On tree row West

7. September 27, 1999, Randy Kolehouse #25854, Kent County Remon LCRC # 11578

Found Standard Kent County Monument 2 +/- feet west of the C/L of Montcalm avenue (gravel) running north and south , on line of a tree row running west, per LCRC's # 4535 and # 7256 as set by John Bueche in place of an iron and stone he found per LCRC Liber 001 Page 518 (Montcalm County)

- Nail/KC remon tag S/S cherry 20" N85°W 48.08 feet
- Nail/KC remon tag S/S tw oak 32" N80°W 25.20 feet
- Nail/KC remon tag SE/S oak 18" S40°W 40.08 feet
- Nail/KC remon tag NE/S oak 32" S35°E 42.19 feet
- Nail/KC remon tag S/S oak 40" S80°E 30.03 feet
- Rerod East 33.15 feet
- C/L gravel road N-S East 2.00+/- feet
- On tree row running west

