

**SURVEY &
REMONUMENTATION**

MAR 11 1998 MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MONTCALM COUNTY

RECORDED

26 Dec 1997 3:38:38 PM

LORI A. WILSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Montcalm (County)	Located in:	Corner Code #
	Eureka	
1. Public Land Survey	Sec 9 T 9N R 8W	E-5, SW Corner
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Tingley, a field surveyor on _____, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
December 6, 1837, Noah Brookfield, Deputy Surveyor, GLO Notes

- Set Post
- White Oak 8" S04°E 3.04 links
- White Oak 9" N48°W 10 links
- 1864, E.H. Jones, from R.D. McNutt's Index Cards
- White Oak 24" N20°50'W 77 links

- F.A. Palmers Notes 9-8, Page 8-12
- New Bearing Tree: 1856 White Oak 11" S50-3/4°W 40 links
- New Bearing Tree: 1864 White Oak 24" N20°50'W 77 links
- Blond Oak 16" S81°E 173 links

April 1894, assumed to be 50 links from Fairground's fence, and 48 links from fence on South side and in range with fence South

- New Bearing White Oak 24" S44°W 44 links
- 1898, E.H. Jones from R.D. McNutt's Index Cards, 9-8
- Iron Stake

July 1905, F.A. Palmer, County Surveyor found my New Bearing Tree of 1856: White Oak now 26" S51-3/4°W, now 25-4/10 feet

At corner, found rotted stake bottom, put down Iron Pipe

- December 1906, J.F. Daoust, Field Book, Page 10, 9-8
- Found Pipe agreeing with bearing tree
- White Oak 26" S51-3/4°W 25-4/10 feet

December 1906, J.F. Daoust, Book 3, Page 1

1912 R.D. McNutt Field Book, Section 16, 9-8

- Gas Pipe
- H.M. Caulkins, Note Cards 9-8
- White Oak 8" S04°E 30.4
- White Oak 9" N48°W 10

- 1930, R.D. McNutt, Index Cards
- Maple 5" West 40.0 feet
- Southwest Corner Main Entrance Northeast 69.5 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Boat Spike in Monument Box and all Herema bearing objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation corner in Monument Box over Boat spike
- P.K. Nail Easterly side Power Pole N10°W 26.75 feet
- Center anchor bolt overhead light
- Northwest Corner Admiral Station Parking Lot S5°E 34.48 feet
- Northeast Corner Chemical Bank Building S45°W 108.08 feet
- Southwest Corner Building N47°E 101.55 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 5/28, 1997

Surveyor's Michigan License No. 30104

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 5-28-97

W.G.T.
William Tingley, PS, Chairman

Liber 3 Page 387

Continued on Back



