

APR 28 1999

**MONTCALM COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED

**SECTION**

For corners in Montcalm (County) Located In: Eureka Township Corner Code # \_\_\_\_\_

1. Public Land Survey Sec 9 T 9 N R 8 W G-3, NE Corner  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

23 APR 1999 11:03:08 AM

LORI A. WILSON  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William Tingley a field surveyor on 4/16/99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

December 6, 1837, Noah Brookfield, Deputy Surveyor, GLO Notes

Set Post

Pine 14" N49°E 14 links  
 White Oak 12" S73°W 46 links

F.A. Palmer, Field Notes, 9-8, Page 8

New Bearing Tree; 1857, Pine 28" S29°E 122 links

H.M. Caulkins, Index Cards, 9-8

Same as Above.

State Highway Project #59032

P.K. Nail 0.50 feet right of Station 53+ 70.76 feet

Southeast Corner Gas Station Foundation N50°E 68.47 feet  
 Center of Top Nut on Fire Hydrant S25°W 58.71 feet

1965, R.J. Crater #16924, Index Card Record

1" Iron in Monument Box

Power Pole S85°W 28.65 feet  
 Power Pole S30°E 46.0 feet

June 1972, Francis E. Spicer, #7877, Liber 464, Page 944, Recorded Survey

1" Iron in Mon Box

Power Pole S85°W 28.65 feet  
 Power Pole S30°E 46.0 feet

June 1972, Francis E. Spicer, #7877, Liber 1, Page 17, Recorded LCRC

1" Iron in Monument Box

Power Pole S85°W 28.65 feet  
 Power Pole S30°E 46.0 feet

Center "X" N. Lafayette (M-91) and E. VanDeinse Ave. on East Pavement

Continued on Back .....

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1-1/2" Pipe in Monument Box

Power Pole Northeast 55.85 feet  
 Power Pole East Northeast 78.30 feet  
 Power Pole Southeast 55.14 feet

Southeast Corner of Southeasterly

most Metal Support for Gas Station Carport Northwest 79.60 feet

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set Remonumentation Monument over pipe in Monument Box

16 d Nail East Side Power Pole Northeast 55.85 feet  
 R.R. Spike South Side Power Pole East Northeast 78.30 feet  
 P.K. West Side Power Pole Southeast 55.14 feet

Southeast Corner of Southeasterly

most Metal Support for Gas Station Carport Northwest 79.60 feet

This corner is accepted as the best available evidence of the position of the original corner.


Signed by William G. Tingley Date 4/16 1999

Surveyor's Michigan License No. 30104

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4/16/99

WGT  
William Tingley, PS, Chairman



Liber 4 Page 79

umber 11, 1991, William G. Tingley, #30104, Survey  
and 1" Iron in Mon Box Centerline "X" North Lafayette and East VanDeinse Ave.  
Consumer's Power Pole S85°W 28.65 feet  
Consumer's Power Pole S30°E 46.00 feet  
On East Pavement  
1994, A. Brintnall #28407, Survey, Liber 733, Page 1142  
Found 1-1/2" Pipe

16 d Nail East Side Power Pole	Northeast	55.85 feet
R.R. Spike South Side Power Pole	East Northeast	78.30 feet
P.K. West Side Power Pole	Southeast	55.14 feet
Southeast Corner of Southeasterly most Metal Support for Gas Station Carport	Northwest	79.60 feet

**SURVEY &  
REMONUMENTATION**

**APR 28 1999**

**SECTION**

NOTE: Not more than  
on the...

Management of the...  
above were in...  
Court of Law...  
expressed below

Private Claims  
A. Lot No...  
Property in...  
Miscellaneous  
in Section  
Property...