

SURVEY & REMONUMENTATION

SEP 12 1995

COMMISSION

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm (County) Located In: Corner Code #

1. Public Land Survey Sec 15 T 9 R 8 I-7, SE Corner
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 MONTCALM COUNTY
 RECORDED

10 AUG 95 3:29 P.M.

VIRGINIA L. KNEPPER
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on July 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 November 29, 1837, Noah Brookfield, Deputy Surveyor, GLO Notes
 Set Post
 White Oak 14" is corner
 1965, R.D. McNutts, Index Cards 9-8
 George M. Stevenson relocated by government procedure, 1965.
 Set 3/4" T Iron
 Gas marker in fence North 77.21 feet
 Walnut 15" South-Southeast 26.43 feet
 Walnut 12" Southwest 59.30 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No evidence of 14" Oak per GLO
 Found T Iron per George M. Stevenson witnesses, fence north approximately 90 feet North of lake
 Found 1" Iron Pipe 3.5 feet West and 5.0 feet North
 1" Iron Pipe is 2.2 feet Long (both irons are at surface)
 Nothing below either iron

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Remonumentation and Monument Box in place of T Iron
 Set Nail & Tag Eastside 23" Walnut S5°E 26.9 feet
 Set Nail & Tag Northwest side 15" Walnut S45°W 59.9 feet
 Set Nail & Tag Southeast side 15" Oak N25°E 15.32 feet
 Set Nail & Tag South side 24" Oak N88°W 53.34 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 14 MARCH 1995
 Surveyor's Michigan License No. 30104

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 7-29-94

WGT
 William Tingley, PS, Chairman

