

SEP 12 1995

COMMISSION

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm Located In: _____ Corner Code # _____
(County)

1. Public Land Survey Sec. 1 T 10 R 6 M-1 NE Corner
~~Sec 6 T 10 R 5~~ A-1 NDCGR
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED
10 AUG 95 3:30 P.M.
VIRGINIA L. KNEPPER
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Tingley a field survey on March 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- April 5, 1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes
Set Post
Beech 19" S84-1/2°W 56 links
Maple 8" S43°E 18 links
- November 11 and 12, 1890, Edward H. Jones, County Surveyor, Surveyor Notes, Book 2 Page 14
New Bearing Tree: Pine Stump 30" S25-1/2°W 61 links
- March 31, 1913, E. Duff Youdan, County Surveyor
Reset Corner (South 1/4 31, T115-R5W) 14 links West of Township Corners 10-5 and 10-6
M.C.H. 1923, from R.D. McNutt's Card file
Plow Point
Red Oak 8" N70°E 74.04 feet
White Oak 8" N70°W 74.00 feet
- July 1, 1925, Michigan State Highway Dept., M-43 Proj. 11
Corner Not Found
- 1925, Michigan State highway State Trunkline 45, Project 5
Plowpoint 9.3 feet East of south 1/4 Corner Section 31 11-5
White Oak 8" N70°W 74.00 feet
Red oak 8" N74°E 74.00 feet
- About 1970, G.M. Stevenson #13600, Index Card Record
Plowpoint
Red Oak N70°E 74.00 feet
- August 16, 1990, W.G. Tingley, #30104, Recorded Liber 2, Page 332
Found Capped Iron 1.5 feet South and 2.5 feet West of Centerline "X"
* Found Nail in Eastside 8 inch Quad Oak S20°E 75.5 feet
Top Center of Right of Way Marker S85°E 82.0 feet
Fence Line to Northwest 5.0 feet
Street Sign S45°W 38.75 feet



ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4-17-95

W.G. Tingley
William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" Rod in Monument Box 9.25 East of South 1/4 Corner, Section 31, T11N-R5W on the extension of a line from Southeast Corner, Section 1 and the East 1/4 Corner of Section 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Corner in place of 1/2" Rod in Monument box.
Set Nail in Eastside 16" Quad Oak S20°E 75.5 feet
Top Center of Project marker S55°E 82.08 feet
Nail and Tag in Northwest side Power Pole S45°W 54.55 feet
Bottom Southwest Corner Telephone Box N25°W 39.36 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 14 APR 95

Surveyor's Michigan License No. 30104