

SURVEY & REMONUMENTATION

FEB 19 1999

SECTION

**MONTCALM COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

359 ✓

For corners in
Montcalm (County)
Located in: Crystal Township
Corner Code #

1. Public Land Survey	Sec. 5 & T10N	R. 5 W	C-1
	6 T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED
17 DEC 1998 2:14:38 PM
LORI A. WILSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William Tingley a field survey on June 22nd, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- May 17, 1832, O. Risdon, Deputy Surveyor, GLO Notes
Set Post, 1 chain 81 links East of 1/4 Post T11N R5W
Beech 14" S34°E 31 links
Beech 14" S80°W 49 links
 - July 1, 1925, Michigan State Highway Department, M-43, Project 11
No Corner in Plans
 - April 16, 1990, G. Gray #17741, Recorded Liber 2, page 324
Found Monument Box 2.9 feet North of Centerline Road and on Fence Line to South
Elm 12" Southeast 58.0 feet
East Edge Gas Pipeline Marker South 54.21 feet
West Edge Telephone Marker Post West Southwest 35.54 feet

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4/15/98.

WGT
William Tingley, PS, Chairman

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 5/8" Rod, two feet North of Center Line 20 feet bituminous pavement East and West and on fence and treeline to South

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set Remonumentation Monument over Iron
 - Center Line Elm 3" N25°E 45.93 feet
 - Nail in End Fence Post (10" Center Post) South 34.71 feet
 - Capped property iron (#17741) N75°W 100.58 feet
 - D-13, 11-5 (Remonumentation Monument) West 94.82 feet
 - Set Nail and Tag in West Side 24" Stump S45°E 57.18 feet

This corner is accepted as the best available evidence of the position of the original corner.



Signed by William G. Tingley Date 4/15/98
Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983