

DEC 19 2000

MONTCALM COUNTY REMONUMENTATION PROGRAM

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970


For corners in Montcalm (County)

Located In:

Corner Code #

Crystal Township

Table with 3 columns: Item description, Township/Range/Section, and Corner Code #. Includes items for Public Land Survey, Property Controlling, and Miscellaneous Property.



Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

I, William Tingley a field surveyor on June 7, 2000 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. 1831, Robert Clark, Jr., Deputy Surveyor, GLO notes, West on south boundary Section 33
2. 1908, J.F. Daoust, County Surveyor, Liber 3, page 316
3. No Date, R.D. McNutt Card file Crystal Twp. # 120
4. 1968, Patrick Salisbury in Consumer Power Right of Way Survey

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/11/00

Signature of William Tingley, PS, Chairman



- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Searched the apparent location of the corner. Excavated 3.00 feet x 10.00 feet x 7.00 feet deep and found 1/2" rebar in 1 1/4" pipe next to large stone. Found large stone west approximately 6.00 feet.
C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Set remonumentation pipe in monument box in place of rerod and iron pipe. Set rerod and iron pipe with stone along side of pipe.



LIBER 4 PAGE 304

This corner is accepted as the best available evidence of the position of the original corner

Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" x 30" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104."

Signed by [Signature] Date 10/11/00

Surveyor's Michigan License No. 30104