

SURVEY & REMONUMENTATION

MAR 19 1997

COMMISSION

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

12/3/1996 11:48:19 AM

VIRGINIA L. KNEPPER
REGISTER OF DEEDS

For corners in Montcalm Located In: _____ Corner Code # _____
(County)

1. Public Land Survey Sec. 2 T 10 R 5 I-1 Common
and 3 _____ Corner
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, William Tingley a field surveyor on _____,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1831, O. Risdon, Deputy Surveyor, GLO Notes
Intersected North Boundary, 1 chain 74 links East of 1/4 Section Post (Township to North). Set Post
Black Ash 12" S72°E 56 links
Maple 18" S40°W 54 links
- February 22, 1899, Henry M. Caulkin, County Surveyor, Field Notes, Book 1, Page 78, 10-5, Page 74
Reestablished 1 chain 76 links East of 1/4 Post, South side of Section 35 T11N -R5W
Put down Stone and Iron, Took New Bearing Tree
Maple 7" S60°W 95 feet (no mark)
- July 1, 1925, Michigan State Highway Department, M-43, Project 11, Station 537+
Section Corners Common to 2 and 3, Crystal Township, not located
- 1970, R.J. Crater, #16924 (index cards)
Set Railroad Spike on Township Line
Northwest Corner Steel Shed S45°E 86.6 feet
Telephone Pole S45°W 54.0 feet
Telephone Pole N45°E 56.3 feet
- February 23, 1990, W.G. Tingley, #30104
Found Railroad Spike
Railroad Spike West 114.07 feet
Street Sign Post S45°E 48.2 feet
Westerly Leg Road Sign North 25.2 feet
Top Center Riser Box N45°E 56.00 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rod in Monument Box.

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/8/96


W. Tingley
William Tingley, PS, Chairman

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner over Rod.

Westerly leg Road Sign Post	North	25.2 feet
Center Telephone Box	N45°E	57.45 feet
Corner Post Chain Link Fence	S45°E	47.50 feet
Found Wood Post (telephone box support)	S45°W	57.95 feet

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													



Signed by William G. Tingley Date 10/8/96

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 25, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1993