

SURVEY & REMONUMENTATION

MAY 07 1997

COMMISSION

**MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Montcalm Located In: Crystal Township Corner Code # _____
(County)

1. Public Land Survey Sec 36 T 10 N R 5 W L-13, S 1/4
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED
11/14/1996 4:05:39 PM
VIRGINIA L. KNEPPER
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on August 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:
1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes
1/4 Section Post
Beech 8" N74-1/2°E 18 links
Sugar 4" N76°W 10 links
1891, E.H. Jones, County Surveyor
Run South line and established 1/4 Post
Beech 14" N22°E 51 links
This corner about five links south of Post which has been, I think, recognized as North 1/4 Post, Section 6, 9-5 (error? 1-9-5)
R.D. McNutt, County Surveyor, card file
Records H.M. Caukin 1887. Put down landside and plow point. Record GLO bearing trees. Did not find source Caukin record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Did not find evidence of Monument. Set at midpoint of line between Southwest Corner and Southeast Corner of Section 36, on fence line North and 1.3 feet North of fence line East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Remonumentation Corner,
Steel Fence Post, fence corner South 1.3 feet
Rerod S85°E 10.77 feet
Set Nail and Tag in 6" Oak N70°W 10.10 feet
Set Nail and Tag in 6" Oak S83°W 11.84 feet
North Quarter Corner, Section 1, T9N-R5W West 13.83 feet

This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by William Tingley Date 10/8/96
Surveyor's Michigan License No. 30104



ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/8/96

WGT
William Tingley, PS, Chairman

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993