

SURVEY & REMONUMENTATION

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Montcalm Located In: Corner Code

(County) Evergreen Township

1. Public Land Survey Section Sec T 10 R 6 E-7, Cor


T R
T R
T R

2. Property Controlling in Section S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

4. Lot No. Recorded Plat

5. Private Claims



Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on June 15, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838, Noah Brookfield, Deputy Surveyor, GLO Notes

Set Post Corner of 16, 17, 20 and 21

Pine 18" N71°W 14 links

Beech 12" S72°E 24 links

March 1905, John F. Daoust, County Surveyor, Liber 3, Page 132 and Liber 3 Pages 128, Liber 2, Page 150, and Liber 2, Page 128

Reset 39.96 Chains from Quarter Post Southside Section 17, 59.94 chains from 1/4 1/4 post Southside Southeast Quarter

Section 16, 79.86 feet from Section Corner 8-9-16-17, 79.86 Section Corner 20-21-28-29; Drove 1-1/2" Iron spline

18" long

Pine Stump 24" S58-1/2°E 30-1/2 links

Oak 23" S77-1/2°E 113 links

Field Book 2, 10-6, Page 26

Same Record

Field Book 2, 10-6, Page 30

Same Record

1965, Montcalm County Road Plan, 1965, Project CS 5959

1-3/4" Iron Rod

Hickory 18" N04°E 59.20 feet

Oak 24" N57°W 47.0 feet

Road Name Post S62°W 49.9 feet

(Continued on back. . .)

ACCEPTED BY THE MONTCALM COUNTY SURVEY DEPT GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 6-26-99

WGT
William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3.0 foot long Axle Spline 0.6" below surface of pavement with a diameter of 1 1/2" for the first 1.0 feet.

Found Fence corner post with PK nail S46°W 48.50 feet

Found Cable marker NW corner of post S35°E 53.70 feet

Found Cable box (top center) N45°E 44.10 feet

Found east edge of Stop Sign post N25°W 48.30 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument in place of Axle Shaft

Found Fence corner post with PK nail S46°W 48.50 feet

Found Cable marker NW Corner of post S35°E 53.70 feet

Found Cable box (top center) N45°E 44.10 feet

Found east edge of Stop Sign post N25°W 48.30 feet

This corner is accepted as the best available evidence of the position of the original corner.

Signed by William Tingley Date 6-26, 1999

Surveyor's Michigan License No. 30104



SURVEY &
REMONUMENTATION

DEC 1988

SECTION

A. Continued (E-7, 10-6)

1993, W. Tingley, #30104 in Survey #93525

Found 1-1/2" Solid Iron

P.K. Nail in Top of Fence Post	S45°W	48.48 feet
Stop Sign Post	N45°W	48.77 feet
Southwest Corner Cable Riser Box	N50°E	43.67 feet
Underground Cable Marker	S45°E	53.68 feet

Located at the intersection of Centerline of Roads North-South-East-West
1995, Montcalm County Road Plans

Road Name Post	S45°W	49.80 feet
Guard Post	N45°W	51.40 feet
Guard Post	S60°W	54.30 feet

