

JAN 20 2000

SECTION

MONTCALM COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm # (County)

Located In: Evergreen Twp.

Corner Code: G-7, Sec Corner

1. Public Land Survey Sec 22 T 10 R 6

2. Property Controlling in Section S T R

3. Miscellaneous Property in Sec. S T R

4. Lot No. Recorded Plat

5. Private Claims

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED  
27 DEC 1999 9:38:05 AM  
LORI A. WILSON  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on July 15, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838, Noah Brookfield, Deputy Surveyor, GLO Notes

Set Post Corner of 15, 16, 21 and 22  
 Pine 20" S36°W 9 links  
 Pine 15" N55°E 47 links

1879, F.A. Palmer, Liber 1, Page 125, Record of Minutes of Survey

Found both corners all right (Southeast and Southwest of Section 15)  
 March 1905, John F. Doust, County Surveyor, Liber 1, Page 150 and Liber 3, Page 132. Also Field Book 2, 10-6, page 30.

Found corner, gas pipe with bolt in top end

New Bearing Trees:

Northeast Corner of Moffit's House S43-1/4°W 147-1/2 links  
 Oak 2" N66-1/2°E 58 links

R.D. McNutt's Index Card Records

Same record as 1905

1961, Montcalm County Road Commission, FAS Project, CS5959

Oak 28" Northeast 69.65 feet  
 Walnut 15" Northwest 59.55 feet  
 Ash 15" Southwest 64.25 feet

1988, William G. Tingley #30104, Survey

Found 1" Iron Pipe

Set Nail & Tag in 24" Walnut N20°W 60.38 feet  
 Set Nail & Tag in 32" Red Oak S73°W 66.51 feet  
 Set Nail & Tag in 36" Red Oak N15°E 69.78 feet

1990, W.G. Tingley #30104 in Surveys 4-20, 1990 and 4-9-, 1992

Found 1-1/4" Iron Pipe

Found Nail in westside 30" Oak N25°E 69.34 feet  
 Found Nail in Eastside 20" Elm N45°W 60.46 feet  
 Southeast Corner Riser Box N65°W 54.53 feet  
 Found Nail in northside 26" Oak S65°W 66.74 feet

Located on centerline East-West paved road and 4 feet West of Eastside North-South Gravel Road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" iron pipe

Found old nail, set new nail and tag in 40" oak N23°E 69.90 feet  
 Found old nail, set new nail and tag in 30" walnut N21°W 60.10 feet  
 Found old nail, set new nail and tag in 39" oak S72°W 67.20 feet  
 Found cable riser box, southeast corner S47°W 54.50 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Set standard remonumentation corner in place of 1 1/2" iron pipe.

Found old nail, set new nail and tag in 40" oak N23°E 69.90 feet  
 Found old nail, set new nail and tag in 30" walnut N21°W 60.10 feet  
 Found old nail, set new nail and tag in 39" oak S72°W 67.20 feet  
 Found cable riser box, southeast corner S47°W 54.50 feet  
 Set nail and tag in guy pole N48°W 55.50 feet

This corner is accepted as the best available evidence of the position of the original corner.

Signed by William Tingley Date 22 Dec, 1999

Surveyor's Michigan License No. 30104



LIBER 4

PAGE 197