

JAN 20 2000

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION


For corners in Montcalm

Located In: Evergreen Twp.

Corner Code

(County)

- 1. Public Land Survey Sec 15 T 10 N R 6 W H-7, 1/4 Corner
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims



Register of Deeds Stamp & File Number

I, William Tingley a field surveyor on June 15, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: 1838, Noah Brookfield, Deputy Surveyor, GLO Notes

- Set Quarter Section Post in true line
Beech 8" S14°W 14 links
Beech 9" N81°E 9 links

1874, F.A. Palmer, Deputy County Surveyor, Liber 1, Page 24, Record of Minutes of Survey Found bearing tree, made out new one:

- Elm 7" N70°E 4 links

1879, F.A. Palmer, Liber 1, Page 124, Record of Minutes of Survey Found no trace of original 1/4 post on Southside of Section 15. Run line to establish one. Found both section corners all right.

- Made Bearing Trees at South 1/4 Post:
Pine 26" N35°E 19 links
Pine 24" N53°W 15 links

ACCEPTED BY THE MONTCALM COUNTY SURVEY PETER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 1/16/99

1987, W.G. Tingley, #30104

Set at mid-point per county surveyor

1988, W.G. Tingley, #30104

Found Tingley Iron and Cap 6 feet +/- South of Centerline of Sidney Road

- Found Nail in 6" White Oak North 58.18 feet
Set Nail in 10" White Oak S5°W 36.87 feet
Set Nail in 4" White Oak S45°E 44.58 feet Continue on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found 1/2" rebar 0.7 feet below surface of pavement South of centerline Sidney Road
Found nail in West Side of 9" Oak S27°E 54.15 feet
Found Top Center of Cable Riser Box N33°W 48.30 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set remonumentation Monument over 1/2" rerod
Set nail and tag SE side 9" Poplar N50°E 76.58 feet
Set nail and tag SW side 6" Cherry N35°W 78.60 feet
Set nail and tag East side 15" Oak S10°E 37.00 feet
Found nail in west side of 9" Oak S27°E 54.15 feet

This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by William G. Tingley Date 22 Dec, 1999

Surveyor's Michigan License No. 30104

Grid table with columns A-M and rows 1-13. Contains numbers 6-36 and a small circle in cell 7, H.



A. Continued (H-7, 10-06)

1990, W.G. Tingley #30104

Set Corner at mid-point, 1/2" Rerod and Cap
Telephone Box N30°W 57.0 feet
Centerline Road North 7.0 feet
Maple 8" North 58.50 feet

1992, W.G. Tingley, #30104, Reset Corner in Survey 2612,62 feet East of Northwest Corner Section 22 and 2638.11 feet

West of Northeast Corner Section 22 on straight line by extending South 1/4 Corner through fund Center 1/4 Corner

agreeing with internal occupation

Top Center Cable Riser Box N40°W 48.06 feet
Found Nail East Side 10" Oak S20°E 53.95 feet
Set Nail and Tag Westside 20" Maple N10°E 63.06 feet

Located 5.5 feet south of Centerline East-West pavements and 5 feet West of wire fence to South and East; also 5 feet

West of remains of wire fence to north

RECORDATION

JAN 20 2000

SECTION

