

SEP 12 1995

COMMISSION

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Montcalm
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey Sec 2 T 10 R 6 K-1, NE Corner
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

10 AUG 95 3:30 P.M.

VIRGINIA L. KNEPPER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on March 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838, Noah Brookfield, Deputy Surveyor, GLO Notes
 Correction line, Set Post Corner of Sections 1 and 2
 Pine 34" S55°E 19 links
 Pine 7" S65°W 12 links

1925 Michigan State Highway Department plans, Trunkline 45, Project 5
 Ford Axle 0.9 feet North of Centerline of Station 271 and 8.4 (112.9 feet East of South 1/4 Section 36 T11N-R6W)

Courthouse List, No Date
 Ford Axle between two stones, found from old witnesses
 Montcalm County Road Commission Records -- no date
 Found Ford Axle Shaft
 Northeast Corner of East Headwall Southeast 50.6 feet
 Northwest Corner of West Headwall Southwest 50.5 feet
 White Oak 16" Southwest 53.1 feet
 Oak 4" Southwest 85.0 feet
 Pine 7" S65°W 12.0 feet (probably incorrect record of original witnesses)
 Pine 34" S55°W 19.0 feet (probably incorrect record of original witnesses)

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4-18-95

WGT
 William Tingley, PS, Chairman

R.D. McNutt, County Surveyor, Index Card Record

E. Youdan, November 1912
 Double White Oak 18" S7-1/2°W 206 feet 2 inches
 White Oak 10" S46°W 16.4 feet

G.M. Stevenson, Index Card Record

Ford Axle between Stones
 B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 3/4" Pipe in Monument Box
 112.8 feet East of South Quarter Corner, Section 36, T11N-R6W
 White Oak 16" (now 28") S45°W 53.1 feet



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner in Monument Box in place of 3/4" Pipe
 Nail & Tag in Westside of Power Pole N65°W 130.25 feet
 Nail & Tag in Westside of Power Pole N40°E 44.48 feet
 Nail & Tag in Westside of Power Pole S30°E 151.98 feet
 Nail in face of 28" oak S45°W 52.08 feet
 112.8 feet East of S 1/4 Corner, Section 36, T11N-R6W

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date April 19, 1995

Surveyor's Michigan License No. 30104