

SEP 12 1995

COMMISSION

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm Located In: _____ Corner Code # _____
(County)

1. Public Land Survey Sec 1 T 10 R 6 M-1 NE corner
Sec 6 T 10 R 5 A-7 NW corner

2. Property Controlling _____
in Section S _____ T _____ R _____

3. Miscellaneous _____
Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

10 AUG 95 3:30 P.M.

VIRGINIA L. KNEPPER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on March 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
April 5, 1831, Robert Clark, Jr., Deputy Surveyor, GLO Notes

- Set Post
- Beech 19" S84-1/2°W 56 links
- Maple 8" S43°E 18 links

November 11 and 12, 1890, Edward H. Jones, County Surveyor, Surveyor Notes, Book 2 Page 14

New Bearing Tree: Pine Stump 30" S25-1/2°W 61 links

March 31, 1913, E. Duff Youdan, County Surveyor
Reset Corner (South 1/4 31, T11S-R5W) 14 links West of Township Corners 10-5 and 10-6

M.C.H. 1923, from R.D. McNutt's Card file

- Plow Point
- Red Oak 8" N70°E 74.04 feet
- White Oak 8" N70°W 74.00 feet

July 1, 1925, Michigan State Highway Dept., M-43 Proj. 11
Corner Not Found

1925, Michigan State highway State Trunkline 45, Project 5

- Plowpoint 9.3 feet East of south 1/4 Corner Section 31 11-5
- White Oak 8" N70°W 74.00 feet
- Red oak 8" N74°E 74.00 feet

About 1970, G.M. Stevenson #13600, Index Card Record

- Plowpoint
- Red Oak N70°E 74.00 feet

August 16, 1990, W.G. Tingley, #30104, Recorded Liber 2, Page 332

- Found Capped Iron 1.5 feet South and 2.5 feet West of Centerline "X"
- Found Nail in Eastside 8 inch Quad Oak S20°E 75.5 feet
- Top Center of Right of Way Marker S85°E 82.0 feet
- Fence Line to Northwest 5.0 feet
- Street Sign S45°W 38.75 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" Rod in Monument Box 9.25 East of South 1/4 Corner, Section 31, T11N-R5W on the extension of a line from Southeast Corner, Section 1 and the East 1/4 Corner of Section 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Corner in place of 1/2" Rod in Monument box.
- Set Nail in Eastside 16" Quad Oak S20°E 75.5 feet
- Top Center of Project marker S55°E 82.08 feet
- Nail and Tag in Northwest side Power Pole S45°W 54.55 feet
- Bottom Southwest Corner Telephone Box N25°W 39.36 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 14 APR 95
Surveyor's Michigan License No. 30104



ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4-12-95

WGT
William Tingley, PS, Chairman