


SECTION

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Montcalm Located In: Evergreen Township Corner Code#
(County)

1. Public Land Survey	Sec 13	T 10	R 6	<u>M-6, E 1/4</u>
		T	R	
		T	R	
		T	R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	



Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William G. Tingley a field survey on July 15, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1838, Noah Brookfield, Deputy Surveyor, GLO Notes

- 1/4 Section Post
- Black Ash 16" N64°W 12 links
- Black Ash 11" S37°W 57 links

1897, Henry Caukin, County Surveyor, Liber 2, Page 61, Record of Minutes of Survey

- Put down gun barrel and took new bearing tree
- Elm 18" S26-1/2°E 27 links

Field Book 2, 10-6, Page 2

Same as 1897, except Elms is 87 links

R.D. McNutt's Index Card file

- 1970 R.J. Crater found octagon gun barrel
- 36" Silver Maple East 14 feet
- 14" Hickory S35°W 52.3 feet
- 12" Bass Wood S75°W 39.7 feet

Montcalm County Road Commission

Same Record as above

1970, G.M. Stevenson, Jr. #13600, card file

Same record and 106.2 feet North of W 1/4 Section 18, T10N-R5W

1997, W. G. Tingley #30104, Survey #96228

Found corner no witnesses.

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 845 OF 1980 AT A MEETING HELD 7-25-99

WGT
 William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2.0' Long Octagon Gun Barrel 0.5 feet below surface or road 1.0 feet to East of centerline of Senator Road.

At 2.4' below surface of road found evidence of old decayed wooden post directly below gun barrel.

- Found 43" Silver Maple East 13.82 feet
- Found 1/2 Iron 0.5 " below Road surface South 160.2 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner over rotted wooden stake in place of Octagon gun barrel.

- Set nail and tag North side 43" Silver Maple East 13.82 feet
- Set nail and tag SE side 15" Hickory S21°W 45.67 feet
- Set nail and tag NE side 16" Soft Maple N55°W 23.53 feet
- Set nail and tag NW side 32" Hard Maple N24°E 48.55 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 7-25-99, 1999

Surveyor's Michigan License No. 30104

