

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

T 10 11 PM '75

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 10 N. 7 E.	K6;K7;L5;L6;L7
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS

1975 SEP 19 PM 2 22

STATE OF MICHIGAN
COUNTY OF HONOLULU
RECEIVED FOR RECORD

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, George M. Stevenson do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on March-April 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

K6; Moore & Buggink 1965; RR iron, 22" Oak, NE, 27.36'; 15" Pine, SE, 31.89'; Tw 14" Oak, SSW, 44.85'; 18" Oak, W, 52.89'; 1969 R.J. Crater; Found as above

K7; Moore and Buggink 1965 3/4" pipe; TW 10" Oak, SE, 46.33'; Tr 10" Oak, EW, 88.68'; 15" Pop., ENE, 63.17'; Power Pole, ENE, 53.84'; R.J. Crater found as above in 1969

L5; no monument or accessories found

L7; In 1969 R.J. Crater set at midpoint of South section line on a straight line between corners RR spike in top of 1 1/4" pipe near North edge of pavement; 10" Pop, S30W, 59.0 ft; Cut nail in S. end of W. wall abat., Dr. way, N45W, 13.4 ft, Power pole, N30W, 31.00 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K6 and K7; found as above in "A"

L5 Set 1 1/4" pipe at midpoint of North Sec line

L6: Set 5/8" x 18" Steel rod at intersections of quarter lines of Section 13

L7; found as above

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K6; as above. K7; as above.

L6: 5/8" x 18" steel rod, 26" Red Oak, 220°, 46.74 ft; 9" Acer saccharine, 130°, 14.84 ft; 3-10" Silver Maple, 275°, 17.84 ft (directions N. azimuths)

L5; 1 1/4" x 48" pipe; 18" cherry, 330°, 30.80 ft; 5" Maple, 220°, 50.30 ft; 2" pop, 125°, 8.40 ft; (directions North azimuths)

L7; as above

SIGNED BY: George M. Stevenson DATE: May 16, 1975

SURVEYOR'S MICHIGAN REGISTRATION NO: 13600 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ DATE: _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY: _____ DATE: _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

LIBER 1 PAGE 287

PAGE 2