

MAY 07 1997

COMMISSION

MONTCALM COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm Located In: Sidney Township Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey Sec T 10 N R 7 W I-13 S Bdry.  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED  
12/27/1996 2:10:31 PM  
VIRGINIA L. KNEPPER  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William Tingley a field surveyor on November 29, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
1837, Noah Brookfield, Deputy Surveyor, GLO Notes  
80.00 chains - set post corner of 34 and 35  
Black Ash 10" N52°W 37 links  
Elm 10" N71°E 31 links  
November 1837 intersection of north line 19 links East of post.  
R.D. McNutt, County Surveyor, card field records  
E.H. Jones 1883, Black Ash 18" N48°E 75 links  
1994, K. Roosien #31604, LCRC, Liber 3, Page 84  
Found 1-1/2" pipe with fence line running North  
Found 1-1/2" solid pipe 17.16 feet East (corner I-1 of T9N-R7W, GLO specifies 12.54 feet  
Found Nail in Northwest side 8" Elm N45°E 8.35 feet  
Found Nail in Westside 8" Cherry N40°W 31.36 feet
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1-1/2" pipe on Fence North  
Found Nail in 10" Birch N20°W 31.15 feet
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set Remonumentation Monument over 1-1/2" pipe  
Found Nail in 10" Birch N20°W 31.15 feet  
Set Nail and Tag 8" Elm N05°W 8.22 feet  
Set Nail and Tag 10" Elm S85°E 8.14 feet  
Centerline 3" Elm South 2.23 feet

This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by William G. Tingley Date 12-17 1996  
Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 197  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER  
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990 AT A MEETING HELD 12-17-96

WGT  
William Tingley, PS, Chairman

