

# SURVEY & REMONUMENTATION

APR 24 1995

## MONTCALM COUNTY REMONUMENTATION PROGRAM

Corner approved by Peer Group on \_\_\_\_\_, 1994

COMMISSION

### LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED

29 DEC 94 3:13 P.M.

VIRGINIA L. KNEPPER  
REGISTER OF DEEDS

For corners in <u>Montcalm</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Sec. 36 T <u>11</u> R <u>5</u>	<u>L-13 S 1/4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William Tingley a field survey on January 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1831, Robert Clarke, Jr., Deputy Surveyor, GLO Notes

Set Post

Sugar 16" N58°E 34 links

Beech 6" N80°W 28 links

October 10 and 11, 1887, H.M. Caulkin, County Surveyor, Surveyor Notes 36-11-5

Found bottom of Stake in road bed that had been set about 14 years ago (1873). Put down a land side 2 feet long and 3" wide at upper largest end with plow point on southside

July 1970, Montcalm County Road Commission Index Cards

Found iron part of old plow

No witness given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence found of original corner.

Set corner at 107.58 feet West of Corner Post per GLO record of 1 chain, 63 links, common to Section 1 and 2, T10N-R5W, on Fence Line North.

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 7/29/94

William Tingley  
William Tingley, PS, Chairman

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation corner and monument box on Fence Line North.

107.58 feet East to common to Section 1 and 2 T10N-R5W 107.58 feet East.

Nail and Tag 4" x 4" Post, Buried Cable Marker N30°E 39.32 feet

Nail and Tag Power Pole S65°W 134.04 feet

Nail and Tag Power Pole S55°E 91.78 feet

Nail and Tag 4" x 4" Post Buried Cable Marker N25°E 84.11 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 7-30-94

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1983

LIBER 3 PAGE 164