

SEP 1 1993

CONFIRMATION

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey Corner T 11 R 7 _____ A-11, _____ Sec _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 MONTCALM COUNTY
 RECORDED

10 AUG 95 3:30 P.M.

VIRGINIA L. KNEPPER
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on October 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 May 26, 1937, John Hodgson, Deputy Surveyor
 Set Post
 Beech 8" S36°W 28 links
 Beech 8" N14°W 30 links
 1884 H.M. Caulkin, Deputy Surveyor from Surveyor Notes of Montcalm County Register of Deeds
 Found new Bearing Tree of 1878 when Bearing trees were plain: Pine Stump 25" N42-1/2 E 26 links
 Set Fire Clay Mon on Hardpan Blacksmith Cinders around bottom
 August 20, 1923, J.F. Doust, County Surveyor from Surveyor Notes of Montcalm County Register of Deeds
 Corner was inquired of residents and found fire clay mon was plowed out and broken while graveled road was being constructed.
 Drove piece of Gas Pipe and Broken Pump Handle in Center of Cinder
 3" Maple bears N12°W 82.33'
 April 6, 1990, G. Gray #17741, Liber 2, Page 299
 Power Pole N60°W 95.57'
 Guy Pole N20°W 104.3'
 Maple 22" S15°E 102.2'
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Gas Pipe and Broken Pump Handle Set in Nest of Rocks
 Accepted Pipe as I.F. Doust Corner

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 3-19-95

W.T.
 William Tingley, PS, Chairman

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set remonumentation corner and monument box.
 Nail & Tag in Power Pole N60°W 95.57'
 Nail & Tag in Guy Pole N20°W 104.3'
 Nail & Tag in 22" Maple, Westside S15°E 102.20'
 No witness less than 200'

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date MOE 14 1995
 Surveyor's Michigan License No. 30104

