

**SURVEY &
REMONUMENTATION**

SEP 12 1995 **MONTCALM COUNTY REMONUMENTATION PROGRAM**
LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Montcalm
(County) Located In: Corner Code #

1. Public Land Survey Sec 8 T 11 R 7 C-5, SW Corner
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED
10 AUG 95 3:30 P.M.
VIRGINIA L. KNEPPER
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Tingley a field survey on November 14, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
April 1, 1836, Noah Brookfield, Deputy Surveyor, GLO Notes

Set Post
Beech 12" N9°E 39 links
Beech 20" N24°W 64 links

1884, F.A. Palmer, County Surveyor, Field Book, Page 50
Found Stake

Fire Clay Mon - Blacksmith cinders
New bearing tree: pine stump 18" S55-1/2°W 37 links

April 1906, J.F. Daoust, Field Book, page 42

Found fireclay mon. Set stones around mon.
New bearing tree: Pine stump 26" S28-1/4°W 90-1/2 links

Montcalm County Road Commission Files

Power Pole Southeast 73.90 feet
South end of culvert Southeast 38.40 feet
North end of culvert Northeast 47.85 feet
Road name post Southwest 28.75 feet
Steel union post Northwest 69.70 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/2" iron pipe 1.8 feet long. Found fireclay mon in nest of stones and blacksmith cinders.

Found nail power pole S50°E 73.97 feet
Found Nail 10" tree N65°E 79.53 feet
Found South end of culvert S50°E 38.6 feet
Found North end of culvert N75°E 47.70 feet
Found Post for riser box N75°W 69.70 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation corner and monument box over fire clay monument.

Found nail power pole S50°E 73.97 feet
Found Nail 10" tree N65°E 79.53 feet
Found South end of culvert S50°E 38.6 feet
Found North end of culvert N75°E 47.70 feet
Found Post for riser box N75°W 69.70 feet
Dead end sign post S25°W 53.80 feet
Top of 3' x 3' x 2' pointed stone S45°E 47.2 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 15 APR 1994

Surveyor's Michigan License No. 30104

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4/29/95

WGT
William Tingley, PS, Chairman

