

COMMISSION 1-2-1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

For corners in **COMMISSION** Montcalm County Remonumentation Program

Montcalm _____ Located In: _____ Corner Code # _____
(County)

21 DEC 93 3:11 P.M.

VIRGINIA L. KNEPPER
REGISTER OF DEEDS

- | | | | | |
|---------------------------------------|---------|-------------|------------|--------------------|
| 1. Public Land Survey | Sec. 32 | T <u>11</u> | R <u>7</u> | <u>C-12, W 1/4</u> |
| | | T _____ | R _____ | _____ |
| | | T _____ | R _____ | _____ |
| | | T _____ | R _____ | _____ |
| 2. Property Controlling
in Section | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, William Tingley a field survey on October 21, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

March 30, 1839, Noah Brookfield, County Surveyor from Surveyor Notes of Montcalm County Register of Deeds

Set Post

Maple 10" N65°W 11 links

Maple 12" N70°E 21 links

1884, H.M. Caulkin, County Surveyor, from Surveyor Notes of Montcalm County Register of Deeds

Found Stake Hole, both Bearing Trees dead but agreeing with courses and distance

Set Fire Clay monument

Pine Stump 22" N 1/2°E 34-1/2 links

January 21-22, 1915, E. Duff Youdan, County Surveyor from Surveyor Notes of Montcalm County Register of Deeds, Page 80 & 81

Found H.M. Caulkins Fire Clay Monument and Root Stake

Pine Stump 22" N1°E 34-1/2 links

New Bearing Trees:

Oak 4" N58°E 42 links

Oak 4" N40°W 73-1/2 links

March 8, 1915, R.D. McNutt

Found H.M. Caulkins Fire Clay Monument from Book 2 Page 390 Surveyor Notes of Montcalm County Register of Deeds

Pine Stump 22" N1/2°E 34-1/2 links

Oak 4" N58°E 42 links

Oak 4" N40°W 73-1/2 links

Side Note on R.D. McNutt's Files: Oak 20" N39°10'W 48.4, Oak 18" N31°45'E 103.5, No dates or what found given

1960, G.M. Stevenson, County Surveyor, #13600, Liber 1 Page 365

Found Pipe with Standard Disk. Found same again in 1975.

Power Guy Pole N15°W 39.70'

Telephone Pole S20°W 22.30"

4" x 4" Wood Sign

Post S 60°E 50.60'

February 28, 1989, W. G Tingley #30104 from Land Corner Recordation, Liber 2, Page 261

Found 1" Iron

Power Pole S10°W 32.6'

Power Pole North 40.1

Poplar 6" N25°E 55.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Iron S10°W 32.6 Power Pole

Power Pole North 40.1'

Poplar 6" N25°E 55.3'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation corner and monument box.

Nail & Tag Power Pole S10°W 32.6'

Nail & Tag Power Pole North 40.1'


Nail & Tag Poplar N25°E 55.3'

Boat Launch Sign, 4 x 4 Woodpost, S40°E 51.2'

This is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 23 November 1993

Surveyor's Michigan License No. 30104



LIBER 3 PAGE 77