

SEP 12 1995

COMMISSION

**MONTCALM COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm Located In: _____ Corner Code # _____
(County)

1. Public Land Survey Sec 8 T 11 R 7 E-5, SE Corner
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED
10 AUG 95 3:35 P.M.
VIRGINIA L. KNEPPER
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, William Tingley a field survey on February 20, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
March 28, 1839, Noah Brookfield, Deputy Surveyor, GLO Notes

- Set Post
 - Beech 14" N28°W 21 links
 - Beech 12" S52°E 17 links
- July 1869, from R.D. McNutt's Index Cards, 11-7, #40
- Buried Stone 24 x 14 x 9 crockery
- 1884, F. A. Palmer, Field Notes, Page 98
- Found Stone
 - Fire Clay Mon - Blacksmith Cinders
 - Pine Stump 30N53E 60 links
- June 1909, J.F. Daoust, County Surveyor, Book 3, Page 384, also found in Field Book 11-7, pages 67-79
- Found Monument OK from Pine Stump 30" N53°E 60 links
- About 1970, G.M. Stevenson #13600,
- Railroad Spike over Rod
 - Power Pole N45°W 62.40 feet
 - Power Pole N45°E 67.20 feet
 - Sugar Maple 32" N50°E 79.60 feet
 - Road Name Post S35? 35.00 feet
- 14 feet West Centerline Miles Road
- 3 feet South of Centerline McBrides Road

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4-19-95
WGT
William Tingley, PS, Chairman

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Continued on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Railroad Spike over 1/2" x 16" Iron, nothing below 4 feet; Found irons are 2665.44 feet West of South 1/4 corner, Section 9, Youdan's 1909 Measurement was 2664.42 feet) and 2607.57 feet North of West 1/4 Corner Section 16 (Daoust 1909 Measurement was 2608 feet) where we found a plowpoint.

- Found Stevenson's Bearing Trees
 - Nail in Power Pole N45°W 62.50 feet
 - Nail in Power Pole N45°E 67.10 feet
- Accepted as corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Remonumentation Corner in Place of Spike Rod
- Located 14 feet West of Centerline Miles Road and 3 feet south of Centerline McBride Road
- Stop Sign/Street Sign, S70°E 66.5 feet
- Nail in Southside Power Pole N45°E 67.10 feet
- Nail in Westside Power Pole N45°W 62.50 feet
- Stop sign Post N01°W 45.00 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 19 April, 1995
Surveyor's Michigan License No. 30104



A. Continued from front (E-5, 11-7)

April 1989, W.G. Tingley, #30104

Found Railroad Spike

Stop Sign	S45°E	66.25 feet
Power Pole	N45°W	62.46 feet
Stop Sign	N03°W	45.48 feet
Power Pole	N45°E	67.25 feet

1989, W. G. Tingley, #30104

Found Railroad Spike, located 14 feet West of Centerline Miles and 2.7 feet South of Centerline of McBride

Stop sign/street sign	S70°E	66.5 feet
Found Nail Southside Power Pole	N45°E	67.1 feet
Found Nail Westside Power Pole	N45°W	62.5 feet
Stop Sign Post	N01°W	45 feet