

**MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Montcalm
(County)

Located In: Douglass

Corner Code # G-2, E 1/4

| | | | | |
|------------------------------------|---------|---------------|--------------|-------------------|
| 1. Public Land Survey | Sec 4 | T <u>11</u> N | R <u>7</u> W | <u>G-2, E 1/4</u> |
| | | T _____ | R _____ | _____ |
| | | T _____ | R _____ | _____ |
| | | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ | _____ |
| | S _____ | T _____ | R _____ | _____ |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

17 DEC 1998 2:12:02 PM

LORI A. WILSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, William Tingley a field survey on October 31, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
March 27, 1839, Noah Brookfield, Deputy Surveyor, GLO Notes

Set 1/4 Section Post
Beech 10" N21°W 12 links
Beech 6" S24°E 20 links

December 1869, Henry Caulkin, Deputy Surveyor Liber 3, Page 10.

Pine 34" N61°E 63 links
1884, preserved by New Bearing Tree of 1869, Liber 1, Page 387, Record of Minutes of Survey
Set Fire Clay Monument and Blacksmith Cinders
Elm 12" N89°E 97 links
Elm 5" S32°E 86-1/2 links

May 30, 1909, John Daoust, County Surveyor, Liber 3, Page 376, Record of Minutes of Survey

Found monument and crockery from Bearing Tree Pine Stump N61°E 63 links
Set Stone over Monument
Elm 12" N89°E 97 links
Elm 5" S32°E 86-1/2 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" x 12" Solid Axle Spline .3 feet below road surface. At 1 foot below surface, found nest of stone and broken crockery and blacksmith cinders around fire clay monument. Replaced axle over top of fire clay monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument over Fire Clay Monument

Found Nail in Southeast side Power Pole S40°W 51.24 feet
Found Nail in North side Power Pole S70°E 48.38 feet
Set Nail and Tag South side Power Pole N75°W 72.42 feet
Set Nail and Tag East side Power Pole N20°W 82.60 feet


Liber 4 Page 37

This corner is accepted as a careful and faithful perpetuation of the position of the original corner

Signed by William Tingley Date 4/6/99, 1998

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983



WGT
William Tingley, PS, Chalman

374 ✓

**SURVEY &
REMONUMENTATION**

FEB 19 1999

SECTION