

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm (County)	Located in: Douglass Township	Corner Code # I-12
1. Public Land Survey	Sec T 11 N R 7 W	I-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec:	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

17 DEC 1998 2:11:45 PM

LORI A. WILSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William Tingley a field surveyor on November 6, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Noah Brookfield, Deputy Surveyor, GLO Notes

40.00 chains, Set Quarter Section Post

Beech 10" S82°W 35 links

Beech 12" N79°E 44 links

1877, F.A. Palmer, County Surveyor (Survey in 34), Liber 1, Page 78-79, Record of Minutes of Survey

Made new 1/4 Post on Eastside of Section by running the Section line. Set stake from which

Maple 6" bears N13°W 34 links

Pine 30" bears S36°W 27 links

1884, H.M. Caukin, County Surveyor, Liber 1, Page 385 (Corners Remonumented in Douglass Township), Record of Minutes of Survey

Quarter Post 34 and 35; found stake and remains agreeing in course and distance with field notes of bearing trees. New bearing tree:

Pine Stump 28" S39-1/4°W 26-1/2 links

(Set Fire Clay Monument with Blacksmith Cinders)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Fireclay Monument below road surface. Left bottom 1/2 of Fireclay under Remonumentation Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument over Fireclay Monument.

Center Telephone Cable Box N85°E 32.73 feet

Found Nail & Tag Northside Power Pole S85°W 51.92 feet

Found Tail & Tag Southside Power Pole East 78.31 feet

Center of 8" Maple (no nail) N45°W 88.81 feet

Liber 4 Page 36

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 2/18/99 1998

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1983



ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 2/19/99.

WGT
 William Tingley, PS, Chairman

SURVEY &
 REMONUMENTATION

FEB 19 1999

SECTION