

# SURVEY & REMONUMENTATION

1993

## LAND CORNER RECORDATION CERTIFICATE

**COMMISSION**

**Filing Requirement of Act 74, Mich. P.A. 1970**  
Montcalm County Remonumentation Program

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED

For corners in

MONTCALM  
(County)

Located In:

Corner Code #

21 DEC 93 3:11 P.M.

VIRGINIA L. KNEPPER  
REGISTER OF DEEDS

- |                                    |                                |                      |       |
|------------------------------------|--------------------------------|----------------------|-------|
| 1. Public Land Survey              | Sec. 34 T <u>11</u> R <u>7</u> | <u>I-13 S. Edry.</u> |       |
|                                    | and 35 T _____ R _____         | _____                | _____ |
|                                    | T _____ R _____                | _____                | _____ |
|                                    | T _____ R _____                | _____                | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____        | _____                | _____ |
|                                    | S _____ T _____ R _____        | _____                | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____        | _____                | _____ |
|                                    | S _____ T _____ R _____        | _____                | _____ |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on October 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

December 8, 1836, Noah Brookfield, Deputy Surveyor from GLO notes  
80.0 West of Post, 35 and 36 South Boundary, T11N R7W calls out 8" Beech ls corner post to 34 and 35 T11N R7W  
August 8, 1877, F.A. Palmer, Deputy Surveyor, Book 1, Page 78 of County Surveyor Book of Montcalm County at Register of Deeds  
Failed to find South Quarter or Southeast Corner (34-11-7) or anything of Corners for Township to South.  
Established South Quarter and Southeast Section Corner by running line from Southwest Corner 34-11-7 to Southeast Corner Section 35-11-7.  
Established individual Corners at their proportionate distance from each other:  
Southeast corner New Bearing Tree Pine 22" N 63°E 8 links  
1884, H.M. Caulkin, Deputy Surveyor, Book 1, Page 369 of Surveyor Records of Montcalm County at Register of Deeds  
Reestablished Corners 160.16 chains from Southeast Corner 36 T11N R7W and 80.08 chains from Corner 33 and 34 T11N R7W  
and on straight-line between Corners 2 and 3 and 3 and 4 North Boundary T10N R7W  
Set Fire Clay mon and Blacksmith cinder  
New Bearing Tree: Pine Stump 20" S43°E 56.5 links  
September 13, 1909, J. E. Youdan, County Surveyor from Field Book 11-7, Pages 72 and 73 at Montcalm County Register of Deeds  
Call out: found Fire Clay mon, leaving no witness  
1939, R.D. McNutt, MCRC index card records at Tingley and Associates Offices  
Found Fire Clay mon  
Maple 6" N41-1/4°W 43.6'  
Oak 10" S32°E 41.0'  
Elm 20" N19°E 89.5'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found Axle Shaft and Hub .5' below surface 2.3' long - 2.9' below surface  
Found Fire Clay mon  
Accepted as corner


**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set Remonumentation Corner and Monument Box.  
Nail and Tag West Side Power Pole N40°E 94.48'  
Nail and Tag West Side Power Pole S10°W 39.9'  
Nail and Tag West Side 12" Walnut N68°W 84.98'  
East Leg Road Sign South 29.0'

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G Tingley Date November 23 1993

Surveyor's Michigan License No. 30104



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993