

APR 28 1999

**MONTCALM COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in  
Montcalm (County)  
 Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 Day Township \_\_\_\_\_

1. Public Land Survey Sec T 11 N R 6 W A-8  
 T 11 N R 7 W M-8 ✓  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 MONTCALM COUNTY  
 RECORDED  
 27 APR 1999 8:27:06 AM  
 LORI A. WILSON  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field survey on October 9, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837, John Dodgson, Deputy Surveyor, GLO Notes

Set Quarter Section Post

Beech 15" S48°W 25 links  
 Beech 10" N84°W 36 links

1884, Henry Caukin, Deputy Surveyor, Liber 2, Page 323, Record of Minutes of Survey

Found stake and remains of trees corresponding with Bearing Trees in course and distance. Nothing available for new bearing trees; stake 1-1/2 rods South; fire clay monument and blacksmith cinders.

1905, John Daoust, County Surveyor, Liber 3, Page 136, Record of Minutes of Survey

Found corner which was part of stones; drove gas pipe 1-1/4" x 4 feet. New Bearing Trees: Pine Stump 24" S36-3/4°W 135 links

R.D. McNutt, County Surveyor, Index Card Records

Same data

1963, Norman Caldwell, #12018, State Highway Department Records, Form 280

Found 3/4" bar in monument in Centerline East-West Road; fence line North

14" Hickory S10°W 97.33 feet  
 Power Pole N66°W 103.27 feet  
 Southeast Corner House Foundation N25°W 86.39 feet  
 Southwest Corner House Foundation N38°W 108.62 feet

1973, George Stevenson, Jr. #13600, LCRC, Liber 1, Page 117

Found above Highway Department witnesses. 3/4" bar and fire clay monument.

1996, William G. Tingley, Certificate of Survey

W1/4 corner section 19, T11N-R6W

Southeast Corner House Foundation N25°W 86.43 feet  
 Southwest Corner House Foundation N42°W 108.65 feet  
 Found Nail in Southeast Face of 14" Hickory N62°E 37.98 feet  
 Set Nail and Tag in West Face of 16" Hickory S08°W 97.44 feet  
 Set Nail and Tag in South Face of Power Pole N70°W 103.43 feet

ACCEPTED BY THE MONTCALM COUNTY SURVEYOR GROUP AS THE OFFICIAL CORNER UNDER PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4/16/98

WGT  
 William Tingley, PS, Chairman

Liber 4 Page 88 372

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/2" Bar and Fire Clay Monument 0.2 feet below surface in Centerline Hillis Road at Intersection of occupation line South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard Remonumentation Monument

Southeast Corner House Foundation N25°W 86.43 feet  
 Southwest Corner House Foundation N42°W 108.65 feet  
 Found Nail in Southeast Face of 14" Hickory N62°E 37.98 feet  
 Set Nail and Tag in West Face of 16" Hickory S08°W 97.44 feet  
 Set Nail and Tag in South Face of Power Pole N70°W 103.43 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 4/16, 1998  
 Surveyor's Michigan License No. 30104

