

APR 28 1999

MONTCALM COUNTY REMONUMENTATION PROGRAM

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED

23 APR 1999 11:03:35 AM

LORI A. WILSON  
REGISTER OF DEEDS

For corners in  
Montcalm  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 11 N R 08 W

A10

T 11 N R 09 W

M10

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No.

Recorded Plat

5. Private Claims

I, William G. Tingley, in a field survey on February 11<sup>th</sup>, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

**1837, J.Hugson, G.L.O. Notes**

set 1/4 sec post

Maple 10"

S34°W 18 Links

Maple 8"

N56°W 31 Links

**September 20<sup>th</sup>, 1892, Edward H. Jones, County Surveyor Notes.**

Section 30 T11N of Range 8 W

NBT Quarter post West side

Pine Stump 14"

N73°W 17 Links

Pine Stump 40"

N25°E 49 Links

Sketch show corner as being 39.74 chains north of A11 (2,622.84 feet)

**No Date, R.D. McNutt Note Card File #113 11-8**

W1/4 Po Sec 30

Maple 10" S34°W 18 Links

Maple 8" N56°W 31 Links

NBT 1883

Pine Stp 40" N40°E 38 Links

May 1916 Wooden stake

Maple 6" S48°E 42 1/2 Links

**06/14/91, William G. Tingley, Certificate of Survey and Field Notes.**

W1/4 Cor. Sec. 30, T11N-R8W,

Found pk - Verified that it was on line & even split from SW-NW

Set nail NE side P.P. S50°E 84.32'

Nly leg Rd. Sign West 23.90'

Nly leg Stop Sign Post N60°E 39.70'

Loc. Centerline N-S Rd. & N.Side Rd. to East

**10/03/91, Charles E. Fricke, Certificate of Survey**

W.1/4 Cor. Of Sec. 30:

P. Pole S40°E 84.3'

Util. Pole N25°W 183.35'

Tel. Pole N60°E 68.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**Found 1/2" Iron & Cap, Yellow Cap partially illegible, Could only read first 2 number "39".**

North leg Arrow sign West 23.82 Feet

North leg Stop sign N75°E 39.75 Feet

Found Nail & Tag #17741 S. side P. Pole S30°E 85.82 Feet

Found PK East Side Utility Pole N15°W 183.7 Feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Set Standard Remonumentation corner over Iron & Cap.**

North leg Arrow sign West 23.82 Feet

North leg Stop sign N75°E 39.75 Feet

Found Nail & Tag #17741 S. side P. Pole S30°E 85.82 Feet

Found PK East Side Utility Pole N15°W 183.7 Feet

**This corner is accepted as the best available evidence of the position of the original corner.**

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4/16/98

WGT  
William Tingley, PS, Chairman

394  
Liber 4 Page 85

Signed by William G. Tingley

Date 4/16/98

Surveyor's Michigan License No. 30104