

FEB 23 1999

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Montcalm # (County)	Located In:	Corner Code
1. Public Land Survey	Sec T 11 R 8	I-11, Sec. Corner
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED
17 DEC 1998 2:13:22 PM
LORI A. WILSON
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, William Tingley a field survey on January 22nd, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1839, Noah Brookfield, Deputy Surveyor, GLO Notes

- Set Post Corner of 26, 27, 34, 35
- Pine 20" S12°W 22 links
- Beech 10" N39°E 45 links

H.M. Caukin, County Surveyor, No date given

Found stone where corner has been held 25 years or more

1867, R.D. McNutt, Survey Corner Index Cards

- Buried Stone 16 x 9 x 8, glass
- Pine Stump 26" N48°W 50 links

1889

Put stone over stone-piece of horseshoe and crockery

- Pine Stump 24" S64°W 62 links

1923, J.F. Daoust, Liber 3, page 480, Record of Minutes of Survey

- Found stone with "+" on top
- Concrete Headwall Corner Northwest 27.45 feet
- Concrete headwall Corner Southwest 28.70 feet

1931, J.F. Daoust, Liber 3, Page 480, Record of Minutes of Survey

- Northeast corner house Southwest 137.65 feet
- Maple 10" Southwest 88.50 feet
- "V" in Guy Pole Northwest 62.0 feet
- "V" in Power Pole Northeast 44.5 feet
- "V" in Power Pole Southeast 109.50 feet

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE REGISTER UNDER MICHIGAN PUBLIC ACT 345 OF 1970. WITNESS HELD 4/16/98

WGT
William Tingley, PS, Chairman



(continued on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Iron and cap #24598 in mon box over horseshoe and crockery.

- Found Nail and tag Northwest side power pole N55°E 73.43 Feet
- Found nail West side power pole S40°E 120.72 Feet
- Northeast corner porch addition (concrete block) S30°W 137.50 Feet
- Set PK and Tag top guard rail post N45°W 48.72 Feet

Liber 4 Page 41

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Marker in Monument Box over iron and cap.

- Found Nail and tag Northwest side power pole N55°E 73.43 Feet
- Found nail West side power pole S40°E 120.72 Feet
- Northeast corner porch addition (concrete block) S30°W 137.50 Feet
- Set PK and Tag top guard rail post N45°W 48.72 Feet

Signed by William G. Tingley Date 4/16/98 1998

Surveyor's Michigan License No. 30104

REMONUMENTATION

FEB 19 1999

SECTION