

SURVEY & REMONUMENTATION

FEB 19 1998

MONTCALM COUNTY REMONUMENTATION PROGRAM

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

26 Dec 1997 3:40:47 PM

LORI A. WILSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in <u>Montcalm</u> (County)	Located In: Pine Township	Corner Code # _____
1. Public Land Survey	Sec 36 T <u>11N</u> R <u>8W</u> T _____ R _____ T _____ R _____ T _____ R _____	<u>K-13, SW Corner</u> _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, William Tingley a field survey on May 20th, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 December 9, 1836, Noah Brookfield, Deputy Surveyor, GLO Notes
 Set Post Corner Sections 35 and 36
 Beech 10" N75°E 75 links
 Maple 10" N59°W 69 links
 November 1871, from R.D. McNutt's Index Cards 11-8 (129)
 New Bearing Tree: Pine 26" N39°E 52 links
 January 1895, H.M. Caulkin, County Surveyor, Book 2, Page 39, Record of Minutes of Survey
 Same as above
 June 1977, G.M. Stevenson #13600, Liber 1, Page 378, LCRC
 Set Railroad Spike on town lines at prorated distances by old survey records between found and relocated corners
 Power Pole N50°W 68.1 feet
 Street Name Post S45°W 46.1 feet
 East Leg Direction Sign S7°W 28.0 feet
 1977, G.M. Stevenson #13600, Survey, Liber 504, Page 673
 Power Pole N50°W 68.1 feet
 Street Name Post S45°W 46.1 feet
 East Leg Direction Sign S7°W 28.0 feet
 Also North 1/4 corner Section 2-10-8 East 493.55 feet. Also in Survey 2277A, Set Corner 5262.33 feet West of Southeast corner Section 36 and 2649.03 feet East of South quarter Corner of Section 35
 1992, W.G. Tingley #30104, Field Notes Job 92192
 Found Railroad Spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Railroad Spike
 Found Street Name post S50°W 46.12 feet
 East leg direction sign S 5°W 27.82 feet
 Power pole N47°W 68.1 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Remonumentation Corner and Monument Box over Railroad spike.
 Found Street Name post S50°W 46.12 feet
 East leg direction sign S 5°W 27.82 feet
 Set P.K. Nail and Tag in Northeast side Power pole N47°W 68.05 feet
 Stop Sign N15°W 67.68 feet

This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

Signed by William G. Tingley Date 5/28, 1997
 Surveyor's Michigan License No. 30104

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 5-28-97.

WGT
 William Tingley, PS, Chairman

