

DEC 19 2000
SECTION

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Montcalm (County) Located in: Maple Valley Township Corner Code #

1. Public Land Survey Sec. 31,36 T 11 N R 09 W
T 11 R 10
T R
T R
T R

2. Property Controlling in Section S T R
S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED
26 JUN 2000 9:34:07 AM
LORI A. WILSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, William G. Tingley, in a field survey on May 3, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. December 11, 1836, Noah Brookfield, Deputy Surveyor, GLO notes, West on south side section 31

Set post corner of Ranges 9 and 10 North Town 11 North
Birch 10" N47°E 11 links (7.26 feet)
Birch 10" N50°W 27 links (17.82 feet)

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 6/14/00.

2. July 1895, Henry M. Caukin, County Surveyor, Record of Survey Book 2-A Page 44
At SW corner of section, put down piece of sleigh shoe 22 inches long
No witnesses given

WGT
William Tingley, PS, Chairman

3. December 28, 1903, Henry M. Caukin, County Surveyor, Record of Survey Book 1-A Page 84 and Book 3 Page 100.
Found my iron of 1896 and remains of one Bearing Tree. Put big pine root stake 2 rods north. (Both entries are the same)

4. No date, R.D. McNutt card file T11N-R10W #132 SE corner Section 36 at Tingley and Associates office
1895 sleigh shoe

5. December 1988, Glen S. Hackbardt # 25844, LCRC T11N-R10W M-13 Liber 002 Page 239
Sleigh shoe

Ash 15" N05°W 24.00 feet
Maple 36" S80°W 188.00 feet
CMP N80°W 167.80 feet



6. 1989, William R. Byl # 23502, Survey 22-Mile Road Right of Way MI Bell cable placement
Found sleigh shoe
No witnesses given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found sleigh shoe in two pieces 11" below the road surface. The second piece was 16" below grade on the west side of the first. Both pieces were approximately 9" long. Found evidence of wood at the bottom of the hole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set remonumentation pipe in place of sleigh shoe pieces. Set one piece on the east side of the pipe and the other piece on the west side.

Set N/T N/S maple 36" S88°W 187.52 feet
Set N/T S/S power pole N86°W 167.60 feet
Center E/S cable marker N04°E 37.95 feet
T/C east end CMP N38°E 40.16 feet
Set N/T E/S quad elm 6" S60°W 38.68 feet



LIBER 4 PAGE 249

This corner is accepted as the careful and faithful perpetuation of the position of the original corner.

Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" x 30" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"

Signed by William G. Tingley Date 6/14/00
Surveyor's Michigan License No. 30104