

DEC 19 2000

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in


Montcalm
(County)

Located In:

Maple Valley Township

Corner Code #

E-13



Register of Deeds Stamp & File Number

- 1. Public Land Survey Sec. 32,33 T 11 N R 09 W
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, William G. Tingley, in a field survey on April 28, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. December 10, 1836, Noah Brookfield, Deputy Surveyor, GLO notes.
West on south side Section 33, Sugar 10" for corner of Sections 32, 33.
No witnesses given
- 2. 1989, William R. Byl, # 23502, Field notes 22-Mile Rd Right-of-Way for Michigan Bell Cable Placement
Found nothing for evidence
No witnesses given
- 3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" x 1.10' rerod. Excavated to 2.00 feet and found no other evidence. The road is cut approximately 2.00 feet below the surrounding ground surface. The rerod was in line with an occupation tree line heading north with an old fence line in the tree line.
- 4. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set remonumentation pipe in place of 1/2" rerod.

Set N/T E/S quad poplar 15"	N07°E	31.08 feet
Set N/T N/S maple 44"	S67°E	105.75 feet
Fnd nail SE/S maple 14"	N65°E	43.26 feet
Fnd nail NW/S maple 36"	S72°W	74.94 feet
T10N-R09W D-01	East	184.48 feet

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/11/00

William Tingley, PS, Chairman

his corner is accepted as the best available evidence of the position of the original corner.

earings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" x 30" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"



LIBER 4

PAGE 309

igned by William G. Tingley

Date 10/16/00

urveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 24, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

