

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 19 2000

SECTION

For corners in

Montcalm
(County)

Located In:

Maple Valley Township

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey Sec. 33 | T 11 N R 09 W | F-13 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED
7 NOV 2000 9:12:57 AM
LORI A. WILSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

I, William G. Tingley, in a field survey on April 18, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. December 10, 1836, Noah Brookfield, Deputy Surveyor, GLO notes, West on south side section 33.

Set quarter section post

Beech 14" N19°E 35 links (23.10 feet)
Beech 12" N80°W 45 links (29.70 feet)

2. December 7, 1899, Henry M. Caukin, County Surveyor, Record of Minutes of Survey Book 3 Page 006

Reestablished Put down plow point and pine root stake
No witnesses given

3. 1989, William R. Byl # 23502, Field notes 22-Mile Road Right of Way MI Bell cable placement field notes

Found nothing-set 1/2" rerod
No witnesses given

ACCEPTED BY THE MONTCALM COUNTY SURVEY FEE GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/11/00.

WGT
William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rerod at road surface. Excavated to 3.0 feet and found nothing else. There is an occupational tree line heading north from the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set remonumentation pipe in place of 1/2" rerod.

Set PK/T NE/S power pole N48°W 105.92 feet
Set N/T W/S thornapple 12" N06°E 118.38 feet
Set N/T SW/S maple 32" S63°E 223.23 feet
Set PK/T SE/S cherry 7" N73°E 72.18 feet
T10N-R09W E-01 East 223.96 feet



This corner is accepted as the best available evidence of the position of the original corner.

Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" x 30" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"



LIBER 4 PAGE 310

Signed by William G. Tingley Date 10/11/00

Surveyor's Michigan License No. 30104