


DEC 19 2000

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Montcalm (County) Located In: Maple Valley Township Corner Code # _____



Register of Deeds Stamp & File Number

- 1. Public Land Survey Sec. 34 T 11 N R 09 W H-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William G. Tingley, in a field survey on April 7, 2000 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- December 13, 1836, Noah Brookfield, Deputy Surveyor, GLO notes
West on south side Section 34. Set quarter section post
Beech 10" N85°E 39 links (25.74 feet)
Beech 12" N35°W 38 links (25.08 feet)
 - September 16, 1912, E. Duff Youdan, County Surveyor, Record of Survey Book 2-B Page 127
Reestablished equidistant and 3 feet north of true line bet adj section corners which agreed well with what appeared to be remains of H.W. Caukins witness and surrounding improvements. Set 3" tile and drove iron rod 1/2" x 30" long in center of same. Drove stake 25 feet east and 25 feet north of corner.
 - April 19, 1968, George Stevenson Witness Card File Maple Valley card file # 162 at Tingley and Associates office
S 1/4 corner Section 34
Twin oak 12" & 15" SE 20.60 feet
Oak 8" SW 49.40 feet
Tele cable marker NW 70.50 feet
East end 15" CMP NE 56.70 feet
- ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 6/14/00
- WGT
William Tingley, PS, Chairman
- 1989, William R. Byl # 23502, Survey Right of Way, 22-mile Road, Michigan Bell cable placement
Iron and cap, 297.36 feet west of T10N-R09W G-01
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Searched apparent location of the corner. Found 1/2" x 13" rerod and broken cap at surface of pavement. Found buggy axle 15" below pavement. Found 3" fire clay pipe pieces 27" below pavement on the east side of axle.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set standard remonumentation pipe over buggy axle.
Kent Co. Witness marker S40°W 37.32 feet
East leg "Arrow" sign S08°W 26.90 feet
Stop sign N07°W 55.55 feet
T/C phone box riser East 275.40 feet

This corner is accepted as the careful and faithful perpetuation of the position of the original corner.

Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" diameter pipe with brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"



Signed by William G. Tingley Date 6/14/00
Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 25, 1971
REVISED MAY 14, 1979
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993



LIBER 4

PAGE 245