


DEC 19 2000

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Montcalm (County) Located In: Maple Valley Township Corner Code #

Table with 3 columns: Description (Public Land Survey, Property Controlling, Miscellaneous), Section (34, 35), Township (T, R), Range (11, 9), and Corner Code (I-13).



Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, William G. Tingley, in a field survey on March 24, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1. December 11, 1836, Noah Brookfield, Deputy Surveyor, GLO notes, West on south side Section 35
2. September 16, 1912, E. Duff Youdan, County Surveyor, Record of Survey Book 2-B Page 127
3. No date, George Stevenson Witness Card File T11N-R09W card # 161 at Tingley and Associates office
4. June 4, 1976, George M. Stevenson, Jr., # 13600, LCRC Liber 001 Page 368
5. June 14, 1976, George M. Stevenson, Jr., # 13600, Certificate of Survey
6. 1989, William R. Byl, # 23502, Field notes Survey of Right of Way Michigan Bell cable placement

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 6/14/00

William Tingley, PS, Chairman



- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Searched the apparent location of original corner. Found 1/2" iron pipe at surface of pavement. Excavated 1.10 feet below surface and found boatspike. At 1.44 feet below the surface found 1" x 1.90 feet iron pipe 0.25 feet SE of spike. At 1.80 feet below surface found 1" x 1.30 pipe and wood evidence at 2.10 feet below surface. Total excavation was 2.50 feet deep.
C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Set remonumentation pipe in place of boat spike and iron pipe
Set N/T E/S maple 30" S05°W 43.50 feet
T/C phone riser N65°W 78.65 feet
Set N/T SE/S elm 5" N62°E 45.85 feet
T/C phone riser S73°E 101.15 feet



LIBER 4 PAGE 247

This corner is accepted as the careful and faithful perpetuation of the position of the original corner.

Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" x 30" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"

Signed by William G. Tingley Date 6/14/00
Surveyor's Michigan License No. 30104