

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Montcalm (County) Located In: Maple Valley Township Corner Code #

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED
22 AUG 2000 9:49:02 AM
LORI A. WILSON
REGISTER OF DEEDS

Table with 3 columns: Description, Township/Range/Section, and Corner Code #. Includes entries for Public Land Survey Sec. 35, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Contains numbers 1 through 36.

I, William G. Tingley, in a field survey on April 07, 2000 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. December 11, 1836, Noah Brookfield, Deputy Surveyor, GLO notes West on south side section 35. Quarter section corner Tamarack 18"
2. September 17, 1912, E. Duff Youdan, County Surveyor, Record of Survey Drove well point from H.M. Caukins New Bearing Tree cedar stump, which I found getting old, but nothing to perpetuate from.
3. 1989, William R. Byl # 23502, Survey notes 22-Mile Road Right-of-Way Michigan Bell cable placement field notes. Found concrete monument with 1 prong? -used that location 15" deep No witnesses-382.21 feet east to T01N-R09W I-01



LIBER 4

PAGE 267

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Searched apparent location of the corner. Found 1/2" x 18" rod 0.1 foot below gravel surface. Found 4" x 24" concrete monument with 3 iron prongs 18" below gravel surface. Possible 1938 monument.

4. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with 3 columns: Monument description, Bearing, and Distance. Includes items like Center MI Bell marker, Set N/T N/S pine 14", Fnd square nail E/S PP, Fnd square nail E/S cedar 20", T10N-R09W I-01.

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 8/09/00

Signature of William Tingley, PS, Chairman

his corner is accepted as the best available evidence of the position of the original corner.

Measurements given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" x 30" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"

Signed by William Tingley Date 8/09/00 Surveyor's Michigan License No: 30104

