

**SURVEY & REMONUMENTATION**

**FEB 19 1999**

**MONTCALM COUNTY REMONUMENTATION PROGRAM**

**LAND CORNER RECORDATION CERTIFICATE**

**SECTION**

**Filing Requirement of Act 74, Mich. P.A. 1970**

358 ✓

For corners in <u>Montcalm</u> (County)	Located In:  Township	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>6 W</u>	<u>C-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED  
17 DEC 1998 2:15:00 PM  
LORI A. WILSON  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

I, William G. Tingley, in a field survey on August 15<sup>th</sup>, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	●	5	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

**G.L.O. notes**

North between sections 5 and 6  
40.00 Set quarter section post  
September 25, 1905, J.F. Dust, County Surveyor notes, Liber 3, Page 166,  
Found tile agreeing with N.B.T.  
Pine stp. 22" N50°E 41½ links  
No date, R.D. McNutt, County Surveyor, Card Files, Card #30  
¼ Po 5-6, Found FC. Mon + put stone on top took NBT  
Beech 12" N45°W 6 Links  
Beech 10" S36°E 15 Links

ACCEPTED BY THE MONTCALM COUNTY SURVEY GROUP AS THE OFFICIAL CORNER UNDER MICH. PUBLIC ACT 345 OF 1990 AT A MEETING HELD 2/18/98  
WGT  
William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found clay tile 3.5 feet below surface and south of the centerline of road to the east.

Liber 4 Page 48

C. Description of monument for corner and accessories established to perpetuate localizing the position of the corner:

Set standard remonumentation corner over clay tile  
Set nail and tag #30104 north side power pole  
AZ 269° 23.81 feet  
Set nail and tag north side 8" cherry  
AZ 280° 46.83 feet  
Set nail and tag north side power pole  
AZ 92°18' 255.59 feet  
Stop sign AZ 68° 52.48 feet



This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 2/18/98  
Surveyor's Michigan License No. 30104