

APR 28 1999

MONTCALM COUNTY REMONUMENTATION PROGRAM

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Montcalm</u> <small>(County)</small>	Located In:	Corner Code #
	Day Township	
1. Public Land Survey	Sec <u>T 11 N R 6 W</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED

17 DEC 1998 2:11:10 PM

LORI A. WILSON  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William Tingley a field survey on October 9, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1837, John Milroy, Deputy Surveyor, GLO Notes

Set Post Corner to Sections 17, 18, 19 and 20

Beech 6" S25°E 25 links

Ash 6" N66°W 8 links

R.D. McNutt, County Surveyor, Index Card Records #69

Beech 6" S25°E 25 links

Ash 6" N66°W 8 links

New Bearing Tree, 1883:

Maple 22" N34°W 98 links

1979, D. Whittler, #10070, LCRC, Liber 1, Page 155

Found 3" solid clay tile; set 3/4" pipe under it.

Nail in Northwest Side 8" Hickory S45°W 47.3 feet

South end of West Tube N45°E 30.7 feet

End of Corrugated Metal Pipe N45°W 54.0 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" fire clay monument with 1" iron rod over it 2.1 feet below surface of gravel road; 2.5 feet

East of Centerline Peoples Road and 0.5 feet North of Centerline Cannonsville Road (found 3/4"

iron pipe with fire clay cylinder 0.5 feet below surface and S30°W 1.1 feet from lower fire clay).

Used deeper fire clay as corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument in place of fire clay monument.

Found Nail Southeast face of Power Pole S46°W 51.28 feet

Found Nail Northeast face of Power Pole S39°E 50.49 feet

Set Nail and Tag North face of 4" Walnut S72°E 84.80 feet

Top End Corrugated Metal Pipe N53°E 28.08 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 4/16/98, 1998

Surveyor's Michigan License No. 30104

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4/16/98.

W. Tingley  
William Tingley, PS, Chairman

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	19	20	21	22	23	24							
8													
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1971  
REVISED JAN. 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1983

SURVEY & REMONUMENTATION

Liber 4 Page 33

FEB 19 1999

SECTION

308 ✓