

MAY 07 1997

COMMISSION

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

11/14/1996 4:01:49 PM

VIRGINIA L. KNEPPER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Montcalm (County) Located in: _____ Corner Code # _____
Day Township _____

1. Public Land Survey Sec. 32 T 11N R 6W D-13, S 1/4
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on March 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
December 8, 1836 Noah Brookfield, Deputy Surveyor, GLO Notes

- Set Post
Beech 12" N50°E 21 links
Beech 10" N54°W 30 links
1923, MCH (off R.D. McNutt's index cards)
White Ash 16" N50°E 63.9 feet
Maple 16" N70°W 60.3 feet
1925, Michigan State Highway Dept.
Found Iron Bolt on Centerline -- No witnesses given
Montcalm County Road Commission, index cards -- No date given
Found Iron Bolt and Fire Clay Monument
Maple 24" Northwest 60.05 feet (gone)
Oak 18" Southwest 79.35 feet
Triple Oak 3" Northeast 38.55 feet
Maple 20" Northeast 63.85 feet
1970, R.J. Crater from R.D. McNutt's index cards
Found Bolt
Maple 26" N65°E 64.6 feet
Twin Oak 18" N05°E 40.0 feet
Maple 14" S75°W 64.8 feet

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 10/8/96

WGT.
William Tingley, PS, Chairman


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" Iron Road 16" long -- set over large lag bolt at 1.9 feet deep. lag bolt has a 1-1/2" square head and is 14" long.
Maple 26" (now 28") N55°E 64.70 feet
Twin Oak 18" N05°E 40.0 feet

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Remonumentation Corner over lag bolt.
Set Nail in Southeast side 24" Oak N15°E 39.23 feet
Found Nail in Southeast side 28" Maple N55°E 64.70 feet
Centerline Telephone Box N35°E 45.0 feet
Nail in Southeast side 6" Ash N45°E 49.38 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William G. Tingley Date 10/8/96 1996

Surveyor's Michigan License No. 30104



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1988
REVISED MAY 14, 1988
REVISED JAN., 1990
ADAPTED FOR WORD PROCESSING MARCH, 1990