

APR 26 1999

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

389

SECTION

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

23 APR 1999 11:02:51 AM

LORI A. WILSON
REGISTER OF DEEDS

For corners in Montcalm (County) Located In: Township Corner Code #

1. Public Land Survey T 11 N R 6 W E-2
T R
T R
T R

2. Property Controlling in Section S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, William G. Tingley, in a field survey on August 15th 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Sept. 25th, 1905, J.F.Doust County Surveyor Notes, Liber 3, Page 166.
Reestablished at proportional distances bet. adj. Sec. Cor. Drove piece of buggy axle.
Stp. Fence is 38 links east of corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 2.5' long buggy axle beneath 1"x12" square rod
No passing zone sign AZ 38° 41.6'
Do not pass sign AZ 333° 44.00'
Nail in power pole AZ 239° 40.6'
Northwesterly point on 4' wide rock AZ 120° 40.00'

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4/16/98

WGT
William Tingley, PS, Chairman

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set standard remonumentation corner in place of square rod and buggy axle.
No passing zone sign AZ 38° 41.6'
Do not pass sign AZ 333° 44.00'
Nail in power pole AZ 239° 40.6'
Northwesterly point on 4' wide rock AZ 120° 40.00'



This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 4/16/98
Surveyor's Michigan License No. 30104