

APR 28 1999

MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in <u>Montcalm</u> (County)	Located In: Day Township	Corner Code #
1. Public Land Survey	Sec T 11 N R 6 W	F-3, 1/4 Corner
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED  
17 DEC 1998 2:00:36 PM  
LORI A. WILSON  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Tingley a field surveyor on August 6, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1837, Noah Brookfield, Deputy Surveyor  
39.40 chains Set Quarter Section Post  
Maple 12" S44°W 24 links  
Ash 10" N28°E 13 links
  - 1884, F. Palmer, County Surveyor, Liber 1, Page 143, Record of Minutes of Surveyor  
At North 1/4 Post New Bearing Tree:  
Pine 40" N18°E 75 links
  - 1905, J. Daoust, County Surveyor, Liber 3, page 175, Record of Minutes of Survey  
Found Tile -- drove Gas Pipe by it  
East rail of Pere Marquette Railroad is 49 links West of Corner  
August 1996, Tingley Field Notes  
Could not find monument. Set Corner (During Section breakdown of section 9) in line with Woven Wire Fence East and 49 links plus 1/2 railroad gauge East of Railroad bed per 1905 notes. (established Centerline Grate Northerly and Southerly). Also location is in line with tree row to East. Also found smooth wire fence (down-four strands) North and South 17 feet West of location.

ACCEPTED BY THE MONTCALM COUNTY SURVEY PROFESSIONAL GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 2/15/99

WGT  
William Tingley, PS, Chairman



- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found Iron set August of 1996.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set Remonumentation Monument over 1/2" Rod.
- |   |       |            |
|---|-------|------------|
| Set Nail and Tag South Face Fence Post    | S85°E | 13.40 feet |
| Set Nail and Tag Northeast face 7" Poplar | S25°E | 34.10 feet |
| Set Nail and Tag West Side 4" Elm         | N33°E | 21.58 feet |
| Set Nail and Tag North Side 3" Aspen      | West  | 4.00 feet  |

Liber 4 Page 31

This corner is accepted as the best available evidence of the position of the original corner.  
Signed by William G. Tingley Date 4/18/1998  
Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1978  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1983

FEB 19 1999

SECTION

366