

APR 28 1999

MONTCALM COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

STATE OF MICHIGAN  
MONTCALM COUNTY  
RECORDED

23 APR 1999 11:03:28 AM

LORI A. WILSON  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Montcalm Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County) Day Township \_\_\_\_\_

1. Public Land Survey Sec T 11 N R 6W F-5, 1/4 Corner  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

William Tingley a field survey on August 2, 1996,  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
 on this certificate.

Description of original monument and accessories and/or subsequent restoration:

1837, John Milroy, Deputy Surveyor, GLO Notes  
 West corrected between Sections 9 and 16 39.78-1/2 chains  
 Set 1/4 Section Post

Beech 8" S89°E 7 links  
 Beech 15" N18°E 30 links

1879, F.W. Palmer, County Surveyor, Liber 1, Page 128-129, Record of Minutes of Survey  
 Established corners of Section by proportional measurements from four 1/4 posts.  
 January 1882, F.A. Palmer, County Surveyor, Liber 1, Page 243, Record of Minutes of Survey  
 Used Corners established by H.E. W. Palmer  
 October 1882, F.A. Palmer, County Surveyor, Liber 1, page 309, Record of Minutes of Survey  
 Found all the corners and 1/4 Posts.

No Date, County Road Commission, Card, File Records

Raised to surface 12" Angle Iron  
 Elm 28" S10°E (no distance recorded)  
 Power Pole N30°E (no distance recorded)

1992, William Tingley #30104, Survey #92408

Found 1" x 1-1/2" Solid Iron Bar raised with 1/2" Rerod  
 Set Nail and Tag Westside Power Pole N10°E 43.30 feet  
 Southeast Corner Barn N30°W 115.40 feet  
 Southwest Corner Barn N45°W 161.47 feet

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rerod per Tingley 1992. Bearing Objects  
 2614.39 feet East of Southwest Corner of Section (recorded as 2612.61 by Palmer 1882) and  
 2617.74 West of Southeast Corner. Also found Tingley's 1992 Witnesses.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Monument over iron  
 Found Nail and Tag Westside Power Pole N10°E 43.30 feet  
 Southwest Corner Barn N45°W 161.47 feet  
 Southeast Corner Barn N30°W 115.40 feet

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER  
 GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
 PUBLIC ACT 345 OF 1990 AT A MEETING HELD 4/16/98

WGT  
 William Tingley, PS, Chairman

igned by William Tingley Date 4/6 1999

urveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 ADAPTED FOR WORD PROCESSING MARCH, 1993



383  
 Liber 4 Page 84