

~~SURVEY & REMONUMENTATION~~

AUG 3

MONTCALM COUNTY REMONUMENTATION PROGRAM

Corner approved by Peer Group on _____, 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Montcalm
(County)

Located In:

Corner Code #

- 1. Public Land Survey Sec. 6 T 11 R 10
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

A-2, W 1/4

~~SURVEY & REMONUMENTATION~~

AUG 8 1994

COMMISSION

STATE OF MICHIGAN
MONTCALM COUNTY
RECORDED

17 AUG 94 3:48 P.M.

Register of Deeds Stamp & File Number
VIRGINIA L. KNEPPER
REGISTER OF DEEDS

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, William Tingley a field surveyor on July 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

May 29, 1837, John Hodgson, Deputy Surveyor, GLO Notes

Set Post.

- Black Oak 10" S82°W 30 links
- Cherry 8" N74°W 25 links

1859, no name, no date, Page 19, Field Book at Montcalm County Register of Deeds

New Bearing Tree: White Oak 13" S67-1/2°E 49 links

May 1881, F.A. Palmer, page 282, 283, Book 1

Found Stake and Broken Glass, Mortar and Stones

Found roots of oak and Mr. Haskins said he had seen the cherry standing very near where I wanted it.

Set an iron rod with a hook on top of it.

Page 11, Field Notes, no name, no dates, Field Book at Montcalm County Register of Deeds

- Black Oak 10" S82°W 30 links
- Cherry 8" N14°W 25 links

New Bearing Tree 1859

White Oak 13" S67-1/2°E 49 links

F.A. Palmer, 1882, Iron road with hook on top.

May, 1907, J.F. Daoust, County Surveyor, page 336, 337.

Reestablished on straight line and at proportional distances from adjacent section corners. Drove gas pipe with cobbles.

October 1908, J. F. Daoust, Notes, Pages 78 and 79, Field Books at Montcalm County Register of Deeds

Reestablished on straight line and at proportional distances from adjacent section corners.

Drove gas pipe and set stones around same.

- Oak 16" S15-1/2°W 173-1/2 links
- Oak 16" S75-3/4°E 185-1/2 links

Continued on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 12" long Square Boat spike at road surface

Below spike, found gas pipe in nest of stones, 1.3 feet below surface.

2.5 West of Centerline, North-South Road

7 feet North of Centerline East

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner and Monument Box over gas pipe

- Set Nail in Power Pole N40°W 123.23 feet
- Set Nail Black Oak (dead) 18" S82°W 40.07 feet
- Stop Sign N80°E 41.1 feet
- Telephone Riser Box Top/Center S45°E 59.0 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by William Tingley Date 29 July, 1994

Surveyor's Michigan License No. 30104

LIBER 3 PAGE 126

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD 29 July 94
William Tingley
William Tingley, PS, Chairman



Continued from front (A-2, 11-10)

April 1959, Road Commission Files, 11-10

Iron Stake and Stone

Telephone Pole,	Southeast	65.60 feet
Stump 18"	West	38.45 feet

LIBER 3 PAGE 127