


**MONTCALM COUNTY REMONUMENTATION PROGRAM**  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**DEC 19 2000**

**SECTION**

For corners in Montcalm (County)	Located In: Township	Corner Code #
1. Public Land Survey Sec. 33	T <u>11</u> N R <u>10W</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		



Register of Deeds Stamp & File Number

I, William G. Tingley, in a field survey on May 10, 2000 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. **December 12, 1836, Noah Brookfield, Deputy Surveyor, GLO notes West on south side section 33.**  
 Set section post on south quarter corner of section 33  
 Beech 9" N39°E 7 links (4.62 feet)



LIBER 4

PAGE 261

2. **April 27, 1876, Stone and Seeley Plat Liber 007 Page 030**

Locates the section corner at the centerline of Pine and Quarterline Streets. 280.25 feet east from the center of the Railroad

3. **June 30, 1917, Grand Rapids and Indian Railroad Plans located at Tingley and Associates office**  
 Plans show S¼ of Section 33 approximately 210 feet east of center of tracks

4. **No date, R.D. McNutt, card file, T11N R10W # 122 at Tingley and Associates office**  
 1867 South ¼ po Sec. 33  
 W. Oak 26" N48°W 41 feet

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 8/09/00

5. **July 29, 1977, Paul E. VanKooten, # 8618, LCRC Liber 001 Page 414**  
 Found 2" iron

P.K. S/S P.P.	W-SW	90.49 feet
Spike 12" maple clump	SW	94.25 feet
NW cor. steel bldg.	E-SE	128.70 feet
S edge stop sign post	W-NW	74.82 feet

WGT  
 William Tingley, PS, Chairman

6. **April 26, 2000, Kirk Breitels # 30077, Kent County Remonumentation LCRC # 11808**  
 F-13 Pierson (2" iron per L1 P 414, Montcalm Co. Records) is west 236.94 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Searched apparent location of the corner. Found 2" Iron 8" below surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set remonumentation pipe over 2" iron.

S/S stop sign post	N64°W	56.35 feet
NE cor. steel bldg.	S50°E	65.98 feet
NW cor. steel bldg.	S45°W	45.75 feet
End P.K. N/S P.P.	S83°W	90.16 feet
C/L Northland Drive	West	115.85 feet
C/L old RR track line	West	265.95 feet
T10N-R10W E-01	East	236.94 feet

This corner is accepted as the best available evidence of the position of the original corner.

Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" x 1/2" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"



Signed by William Tingley Date 8/09/00  
 Surveyor's Michigan License No. 30104