

**MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

DEC 19 2000

SECTION

For corners in Montcalm (County) Located In: _____ Corner Code # _____
Township _____


1. Public Land Survey Sec. 33, 34 T 11 N R 10 W G-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property In Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____



Register of Deeds Stamp & File Number

I, William G. Tingley, in a field survey on May 11, 2000 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

- A. Description of original monument and accessories and/or subsequent restoration:
- December 12, 1836, Noah Brookfield, Deputy Surveyor, GLO notes, West on south side of section Black Ash 10" for corner section 33 and 34 at 80.00 chains
 Swamp East 15 chains (990 feet)
 - 1914, R.D. McNutt, card file, Sec cor 33-34 (123)
 Set gas pipe
 Found Black Ash 10" Cor.
 Ironwood 5" N59°E 3.00 feet
 Tamarack 10" S4 1/2°W 29.20 feet
 - April 26, 2000, Kirk Breitels # 30077, Kent County Remonumentation LCRC # 11809
 F-01 NO MONUMENT SET AT THIS CORNER-falls in Ware Lake 232.55 feet east of G-13 Pierson Twp. (Montcalm Co. Mon.



- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Searched the apparent location of the corner. Found 1 1/4" gas pipe 3" below surface at the bottom of hill on the north side of Ware Lake.



LIBER 4 PAGE 262

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set remonumentation pipe over gas pipe 6" above the surface. Set carsonite marker on north side of remon. pipe.
- | | | | |
|-----------------------------|-------|------------|--|
| Found Nail N/S 11" Ironwood | N58°E | 3.00 feet | ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 8/09/00 |
| Found PK NW/S 24" Elm | S57°E | 14.39 feet | |
| Set N/T N/S 12" Birch | N81°E | 20.19 feet | |
| Set N/T S/S 5" Ironwood | S82°W | 10.93 feet | |
| Found Nail W/S 8" Elm | S30°E | 19.17 feet | |

WGT
 William Tingley, PS, Chairman

This corner is accepted as the careful and faithful perpetuation of the position of the original corner.

Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" x 30" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"

Signed by William Tingley Date 8/09/00
 Surveyor's Michigan License No. 30104