

DEC 19 2000

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Montcalm (County) Located In: _____ Corner Code # _____
Township _____


1. Public Land Survey Sec. 34 T 11 N R 10 W H-13
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____



Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William G. Tingley, in a field survey on May 5, 2000 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- December 12, 1836, Noah Brookfield, Deputy Surveyor, GLO notes, West on south side Section 34.
Set corner post at South quarter corner section 34 at 40.00 chains
Beech 9" N22°W 17 links (11.22 feet)
Maple 12" N77°E 15 links (9.90 feet)

- 1914 R.D. McNutt, card file T 11 N R 10 W, S ¼ po Sec. 34
Set gas pipe
W. Oak 12" S84 ¾°W 28.90 feet



LIBER 4 PAGE 263

- April 28, 1983, Burt Wickham Jr., # 17639, Certificate of Survey Liber 580 Page 1220
Found Gas pipe
P.K. W/S 32" Oak West 28.85 feet
P.K. W/S 6" Oak S10°W 23.57 feet
P.K. SE/S 12" Oak S75°W 48.75

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 8/09/00

- March 10, 1987, Glen Hackbardt # 25844, LCRC Liber 002 Page 127,
Found Gas pipe (1 ½")
Oak 36" S84°W 28.90 feet
Oak 8" S30°E 40.85 feet
Oak 5" S5°W 23.60 feet

W.G.T.
William Tingley, PS, Chairman

- June 8, 2000, Kirk Breitals # 30077, Kent County Remonumentation LCRC # 11840
Measured 235.81 feet west to H-13 Pierson (1 ½" iron-per Liber 002 Page 127, Montcalm County) 235.68 feet Glaza-235.79 feet Hackbardt.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Searched apparent location of the corner. Found 1 ½" iron pipe.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set remonumentation pipe over 1 ½" iron pipe.
- | | | |
|------------------------|-------|-------------|
| N/T N/S 48" Oak | N85°W | 28.80 feet |
| N/T E/S 14" Beech | S01°W | 14.83 feet |
| Fnd Nail W/S 10" Maple | S20°E | 29.52 feet |
| N/T S/S 24" Oak | S59°E | 78.82 feet |
| T10N-R10W G-01 | East | 235.81 feet |

This corner is accepted as the best available evidence of the position of the original corner.

Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" x 30" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"



Signed by William G. Tingley Date 8/09/00
Surveyor's Michigan License No. 30104