

SECTION


MONTCALM COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

(County)	Located In:	Corner Code #
1. Public Land Survey	Sec. T 11N R 10W 2 & 3 T R T R T R	I-01
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	



Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William G. Tingley a field survey on July 06, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1837, June 9th, John Hodgson, Deputy Surveyor, GLO Notes
North between sections 2 and 3, 81.00 chains (5346 feet) intersected N Boundary 10 Links East of post, set post corner to sections 2 and 3.
Beech 12" S16.5°W 27 links
Beech 10" S8.5°E 18 links
- 1983, November 2nd, Glen S. Hackbardt, #25844, L.C.R.C. Liber 2 Page 47,
Found 1/8 post between H-1 & I-1, (checked fence to West at 1314.72') Measured East 1314.72' and set 1/2" rerod on line extended from J-13 through I-13 Reynolds Township.
Walnut 10" S25°W 57.00 feet
C.P. S30°W 29.15 feet
Maple 20" N50°W 50.00 feet
Ser. Pole N20°W 80.85 feet
Other Iron East 1.58 feet
(SW cor. Sec 35 Reynolds)
- 1989, December 29th, Kevin Roosien, #31604, Survey #891106, Liber 641, Page 698, NW Corner Section 2, Found Rerod verified previous record.

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 8-18-99


WGT
William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Excavated 3'x4' and 3.5' deep hole, found 1/2" rebar below pavement, found nothing else. Accepted as the best available evidence of the position of the original corner. Excavated 6.5' East 3' x 5' hole nothing found.
- | | | |
|-------------------------------|------------------------|----------------------------------|
| Found nail SE side 19" Walnut | S15°W (recorded S25°W) | 57.10 feet (recorded 57.00 feet) |
| Found nail NW side Power Pole | S30°W | 29.25 feet (recorded 29.15 feet) |
| Found nail NE side 33" Maple | N45°W (recorded N50°W) | 50.15 feet (recorded 50.00 feet) |
| Found nail NE side Power Pole | N15°W (recorded N20°W) | 80.80 feet (recorded 80.85 feet) |
| Found I-13, T12N - R10W | East | 1.55 feet (recorded 1.58 feet) |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Standard Remonumentation Monument in place of 1/2" rebar.
- | | | |
|-----------------------------------|-------|------------|
| Found nail SE side 19" Walnut | S15°W | 57.10 feet |
| Found nail NW side Power Pole | S30°W | 29.25 feet |
| Found nail NE side 33" Maple | N45°W | 50.15 feet |
| Found nail NE side Power Pole | N15°W | 80.80 feet |
| Found 1/2" rebar & Well point | East | 1.55 feet |
| Set nail & tag NW side Power Pole | N41°E | 57.95 feet |
| Set nail & tag NE side 6" Elm | S30°E | 63.15 feet |



Bearings given are magnetic. Standard Monumentation consists of a Berntsen Stainless Steel 30" x 2 3/8" pipe with Brass Cap stamped "Montcalm County Remonumentation" P.S. 30104

Signed by William G. Tingley Date 8-18-99, 1999
Surveyor's Michigan License No. 30104

