

DEC 19 2000

MONTCALM COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Montcalm Located In: Pierson Township Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey Sec. 34, 35 T 11 N R 10 W I-13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 MONTCALM COUNTY  
 RECORDED  
 22 AUG 2000 9:40:45 AM  
 LORI A. WILSON  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William G. Tingley, in a field survey on May 15, 2000  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law, established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- December 12, 1836, Noah Brookfield, Deputy Surveyor, GLO notes, West on south side of section 35  
Tamarack 18" for corner of section 34 & 35 at 80.00 chains
- September 11, 1904, Henry Caukin, County Surveyor, Record of Minutes of Survey sec. 35 T11N R10W  
Found stump of Tamarack, very old stake beside it. Set Cedar stake  
Cedar NE 6.60 feet  
12" Beech N26°E 24.40 feet  
8" Beech N47°W 6.60 feet
- 1914, R.D. McNutt, card file section cor T11N-R10W section 34-35 (#126)  
Set Gas Pipe  
Stump NW 6.50 feet  
N ¼ cor sec 3 T10N R10W E 252.10 feet
- February 22, 1985, Burt Wickham Jr., # 17639, LCRC Liber 2 Page 131  
2" Gas Pipe  
PK N/S 12" Quad Maple S85°E 16.28 feet  
PK W/S 14" Elm North 27.90 feet  
PK W/S 12" Maple N30°W 33.46 feet  
N ¼ cor sec 3 T10N R10W East 252.10 feet
- June 8, 2000, Kirk Breitels # 30077, Kent County Remonumentation LCRC # 11811  
I-13 Pierson Twp. (Montcalm Co. Mon.) West 251.47 feet

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 8/10/00

William Tingley, PS, Chairman



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Searched the apparent location of the corner. Found 1 ¼" Iron Pipe in swamp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set remonumentation pipe over 1 ¼" pipe. Set carsonite marker next to remon pipe.

- Fnd Nail N/S quad Map S78°E 16.33 feet
- N/T 11" Maple S58°W 18.14 feet
- Fnd Nail W/S 16" Maple N31°W 33.46 feet
- N/T W/S 9" Maple N28°E 35.00 feet
- N/T S/S 12" Maple N70°W 5.99 feet
- T10N-R10W H-01 East 251.47 feet



LIBER 4 PAGE 264

This corner is accepted as the careful and faithful perpetuation of the position of the original corner.

Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" x 30" pipe with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"

Signed by: William Tingley Date: 8/09/00  
 Surveyor's Michigan License No. 30104