

MONTCALM COUNTY REMONUMENTATION PROGRAM

DEC 19 2000

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Montcalm


(County)

Located in:

Pierson Township

Corner Code #

1. Public Land Survey Sec. 36	T 11 N R 10 W	K-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	



Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William G. Tingley, in a field survey on May 08, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- December 12, 1836, Noah Brookfield, Deputy Surveyor, GLO notes, West on south side of section 36.
 Set post corner of Sections 35 and 36
 Maple 12" N81°W 17 links (11.22 feet)
 Birch 10" N64°E 12 links (7.92 feet)
- April 20, 1896, H.M. Caukin, county Surveyor, Record of Survey Book 2-A Page 49
 T11N-R10W corner 35,36 south boundary June 1896. Found bearing tree maple blown down NNE from estimated point where bearing spot was measured. S81°E 1.7 links an found bottom of stake, Thence N64°E 12 links and found rotten birch. Took New Bearing Tree
 Pine stump 22" N49½°E 34½ links (22.77 feet)
- December 28, 1903, Henry M. Caukin, County Surveyor, Record of Survey Book 2-A Page 49, Book 3 Page 100, Book 1-A Page 84
 Found my new bearing tree of 1896at comers marked put down iron.
 Pine stump 22" N49½°E 34½ links (22.77 feet)
- December 1988, Glen S. Hackbardt # 25844, LCRC Liber 002 Page 239
 Found concrete monument near centerline "X" E-W road & fence to north also measured 326.12 feet west of N ¼ corner Sec. 2 Nelson Twp.
 Maple 12" N40°W 33.65 feet
 Maple 10" North 37.45 feet
 Ash 5" N40°E 38.85 feet
 Conc. monument East 326.12 feet
- May 15, Kirk Breitels, # 30077, Kent County Remonumentation LCRC # 11842
 Montcalm Co. Monument K-13, T11N-R10W Sec. 36 west 326.18 feet

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 8/10/00

WGT.
 William Tingley, PS, Chairman

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Concrete monument 3" below road surface with an iron bar along the north side of monument. No other evidence found. Concrete monument possibly set in 1938.

C. Description of monument for corner and accessories established to perpetuate locating the position of the

Set remonumentation pipe in place of concrete monument.
 Set N/T W/S poplar 17" S11°E 20.59 feet
 Set N/T W/S maple 7" S47°W 25.60 feet
 Set N/T W/S maple 18" N30°W 33.75 feet
 Set N/T W/S maple 14" N06°E 28.41 feet
 T10N-R10W J-01 East 326.18 feet



This corner is accepted as the best available evidence of the position of the original corner.

Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" diameter with a brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"

Signed by William G. Tingley Date 8/09/00
 Surveyor's Michigan License No. 30104

