

MONTCALM COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

DEC 19 2000

SECTION

For corners in Montcalm (County) Located in: Pierson Township Corner Code # L-13

1. Public Land Survey Sec. 36	T 11 N R 10 W	<u>L-13</u>
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 MONTCALM COUNTY
 RECORDED
 22 AUG 2000 9:49:01 AM
 LORI A. WILSON
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William G. Tingley, in a field survey on May 4, 2000 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- December 12, 1836, Noah Brookfield, Deputy Surveyor, GLO notes, West on south side Section 36**
 Quarter section corner
 Beech 10" N19°E 15 links (9.90 feet)
 Sugar 18" N18°W 9 links (5.94 feet)
 - April 20, 1896, Henry M. Caukin, County Surveyor, Record of Survey Book 2-A Page 49**
 Reestablished quarter post south side section 36, took new corner bearing tree-pine stump 30" N04°W 48 links (31.68 feet)
 And drove gas pipe about three feet long
 - December 28, 1903, Henry M. Caukin, County Surveyor Record of Survey Book 2-A Page 49 and Book 3 Page 100**
 As reestablished by our 1896-put down iron pipe
 - No date, R.D. McNutt card file T11N-R10W # 131**
 Gas pipe 3 feet long
 Pine stump 30" N04°W 48 links (31.68 feet)
 - December 1988, Glen S. Hackbardt, # 25844, LCRC Liber 2 Page 239**
 1/2" rebar
 Apple 6" N05°E 21.04 feet
 C.P. S20°W 236.30 feet
 Maple 30" S80°W 242.25 feet
 Centerline E-W road North 2.50 feet
 - May 15, 2000, Kirk Breitels # 30077, Kent County Remonumentation LCRC # 11843**
 Montcalm County Monument (S 1/4 Sec. 36 T11N-R10W West 374.42 feet)

ACCEPTED BY THE MONTCALM COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 8/29/00

WGT
 William Tingley, PS, Chairman
 LIBER 4 PAGE 266



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Searched the apparent location of original corner. Found 1/2" rerod 4" below the surface of road. No other evidence found.
 Found stump fence line north of corner location

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set standard remonumentation pipe over 1/2" rebar.
- | | | |
|--------------------------------|-------|-------------|
| Fnd Square nail apple 9" | N12°E | 21.49 feet |
| Fnd square nail E/S power pole | S14°W | 236.35 feet |
| Set N/T N/S oak 18" | N86°W | 263.52 feet |
| Set N/T N/S oak 8" | S81°E | 226.77 feet |
| T10N-R10W K-01 | East | 374.42 feet |



This corner is accepted as the best available evidence of the position of the original corner. Bearings given are magnetic. Standard remonumentation pipe consists of a Berntsen stainless steel 2 3/8" pipe with brass cap stamped "MONTCALM COUNTY REMONUMENTATION, P.S. # 30104"

Signed by William Tingley Date 8/09/00
 Surveyor's Michigan License No. 30104